NEW SOUTH WALES DEPARTMENT OF LANDS

REGULATIONS

FOR THE

EMPLOYMENT OF LICENSED SURVEYORS

1914

Caution:

This document has been prepared by scanning the original 1914 Regulation for the Employment of Licensed Surveyors and using optical character recognition software to create text. There may be scanning and character identification errors within this document. Care has been taken to correct errors in reproduction, however, if there are any doubts to the correct description, reference to the original 1914 text should be made to verify the authenticity of the text.

1608:1-a

INDEX

Subject.	Paragraph.	Page.
Abbreviations -		
Not to be used in reference to corners	178	12
Not to be used in title to plan	179	12
Not to be used in reports - except those recognised [Appendix J]	206	14
Absence from District - District Surveyor to be notified	9	1
Access to water supply - To be provided	44	3
Accounts -		
To be transmitted to District Surveyor	3	1
Stoppage of advances on	5, 15	1-2
For tracings of Real Property Act surveys to be on Form A	246	17
Advance of 75 per cent. may be paid	221, 249	15, 17
For survey of town allotments - to be subject to 10 per cent.		
Decrease	225	16
Printed forms will be supplied for	243	17
Portion surveys - lengths to be given	244	17
For inspections and reports not made at time of survey to be on		
Form B	245	17
Surveyor to have bank account	247	17
Authority to pay into bank required	248	17
To be rendered separately for each survey	250	17
Payment at daily rates	251	17
For daily rates, may be reduced	252	17
To be rendered during financial year	253	17
Surveyor to be informed of alterations	254	17
Claim for correction, reduction, or omission - time limit	255	17
Act of Parliament - Required by a surveyor	4	1
Agricultural capabilities – To be given in field notes	35	2
Alienated land - Owner or occupier to be notified before entry on	16	2
Alignment of streets - Instructions for. [Appendix D]	81	5
Alignment stakes -		
Dimensions of, in marking	96	7
For marking of country portions	115	8
Allotments -		
Submission of measured	61	4
Marking of corner of, [Appendix T]	110	7
Scale to be plotted on plan	149	10
Boundaries of - How to be shewn on plan	155	10
Amendment of surveys - Cost to be paid by surveyor in default	11	1
Angle - Closing to be observed and noted in field notes	29	2
Angles in road surveys - Stakes to be inserted	122	8
Angles - Bearings to be clearly shewn in field notes	27	2
Appendices - To be part of Regulations	256	17
Applicant -		
Consent to be obtained to modification of survey	72	5
Name of to be written in full on plan under title	180	12
Area -	- 5 0	- -
Town and suburban lands, limit of	38	3
Adjustment of errors in	67	4
-J	<i>-</i> ,	•

Subject.	Paragraph.	Page.
Deficiency in, not permitted	69	5
To be written on plan of a portion	175	11
Omission or fractional quantities	177	11, 12
Computation of, to be furnished. [Appendix G]	188	12
Azimuth -		
Comparison of, directions for	54	4
To be shewn, of portions connected to	58	4
To be determined of difference with trigonometrical survey	92	6
Payment for comparison of	233	16
Bearings -		
To be shewn in field notes	27	2
To trigonometrical stations, to be recorded	63	4
From isolated portions to conspicuous natural features	66	4
For feature surveys	83, 120	6, 8
For trigonometrical connections	89	6
To magnetic meridian	145	10
Method of noting on plans	156, 159	10
Of lines not chained, method of noting on plans	160	11
Seconds of are to be omitted	177	11, 12
Boundaries -		
Of portions fronting watercourses	39	3
To be directed to cardinal points	41	3
Where inaccessible, connecting traverse to be made	42	3
To be defined by right lines when cliff forms a barrier	43	3
As to re-marking of	118	8
Marking of County. [Appendix T]	121	8
Of portions and allotments, to be shewn by black lines	155	10
To be shewn on plan as found	168	11
Of Counties, Parishes, &c. Method of indicating on plans.		
[Appendix U]	176	11
Payment for measurement and marking of	222	15
Cancelled surveys - Obliteration of marking	118	8
Capital value of land - To be noted in field notes	37	2
Cardinal points - Boundaries to be directed to	41	3
Cemeteries -		
Instructions for survey and marking. [Appendix E]	95	6
To be indicated on plan by yellow colour	159	10
Cliff forming boundary - To be defined by right lines	43	3
Close of survey-		
To be tested by latitude and departure	68	5
Limit of allowable error in	68	5
Coast line - Rate of payment for survey of	226	16
Colours - List of, to be used on plans	159	10
Comparison of azimuth - Payment for	223	16
Computation of area - To be furnished by surveyor. [Appendix G]	188	12
Conditional purchase-		
Starting point of survey to be shewn on plan	70	5
Purposes for which reserves may be made from	71	5 5
Modification in form of survey	72	5
Conditional lease - starting point of survey to be shewn on plan	70	5

Subject.	Paragraph.	Page.
Connections-		
To be made to previous surveys	58, 65	4
In subdivisions of measured portions	62, 231	4, 16
Across a watercourse	64	4
Required in road surveys	79	5
Required in feature surveys	84, 86	6
With a trigonometrical station	88	6
Marking of. [Appendix T]	121	8
To be written on plans	162	11
To roads intersecting boundaries	167	11
Remuneration for survey of	227, 231	16
Contract - Surveys may be let by	241	16
Co-ordinates - To be shewn on plans of road and feature surveys	174	11
Copper tacks - For marking in feature surveys. [Appendix T]	120	8
Corners -		
Fixation of, near a watercourse	39	3
Marking of section. [Appendix T]	109	7
Marking of allotment. [Appendix T]	110	7
Marking of, in rock. [Appendix T]	111	8
Marking of, in country portions. [Appendix T]	116	8
Particulars of old - to be given on plan as found	169	11
Reference on plan to be in tabular form without abbreviations	178	12
Payment for marking	223	15, 16
Payment for obliterating, in cancelled surveys	224	16
Corner trees-		
Marking of in surveys	100	7
Reference to, to be shewn in field notes	30	2
Correspondence -		
To be transmitted to the District Surveyor	3	1
Forms of letters. [Appendices Wa, b, c, d, e]	201	13
Heading of letters	202	13
Letter transmitting plan to give full particulars of survey	203	13
Letter to be restricted to one subject	204	13
To be dated and numbered consecutively	204	13
To be addressed to the District Surveyor	204	13
Corners of papers not to be turned up	204	13
Instruction number to be quoted when replying to	205	14
Abbreviations not to be used in - except those authorised.		
[Appendix J]	206	14
Envelopes to be endorsed	207	14
Original papers to be returned	208	14
Action taken to be endorsed on papers	209	14
B.C. reports to follow next to instructions	210	14
Register of instructions to be kept by Surveyor	211	14
Register to be supplied by the Department	211	14
Register to be forwarded to District Surveyor when demanded	211	14
County boundaries-		
Marking of. [Appendix T]	121	8
Method of indicating on plans. [Appendix U]	176	11
Country portions-		
· ·		

Subject.	Paragraph.	Page.
Offsets not to exceed 150 links	59	4
Clearing of boundary lines	113	8
Marking of	113-118	8
Positions for special marks	133	9
Scale of plans of	151	10
Creek-	-	-
Separating portions - connection required	64	4
Position of, to be shewn on plan	163	11
Name of to be written on plan	172	11
Crown leases-		
Miners' rights. Within, not to be marked	45	3
Position of miners' rights to be shown on plan	45	3
Area of mining occupation to be excluded from area of	45	3
Co-secants-		
To be stated when road is 3 chains wide or over	166	11
Payment for	228-230	16
Daily rates-Remuneration by	242	16
Deficiency in Area - Not permitted	69	5
Deputy - Employment of, prohibited	6	1
Descriptions - Connections required for preparation of	58	4
Destruction of survey mark - To be reported. [Appendix F]	137, 138	9
Diagrams-	- · ,	
To be provided in field notes, to illustrate same	22	2
To accompany instructions	46, 75	3, 5
On road plans	191	13
Direction Stakes-Position for. [Appendix T]	103	7
District Increase - Payment of	240	16
District Surveyor -		10
Definition of term	1	1
Authority to issue instructions	2	1
All official correspondence to be forwarded to	3, 204	1, 13
May authorise use of instrument other than theodolite	7	1
To be referred to as to measurement if surveyor is in doubt	40	3
Proposed modification of survey to be reported to	72	5
To be referred to re modification of design	73	5
To direct special marking	136	9
May authorise advance on accounts	221	15
To be referred to in cases not provided for in regulations	257	17
Drains-Reserves to protect	52	3
Drawings -	32	3
Plan may be rejected if faulty	12, 144	1, 10
Plans to be of best mounted hand made drawing paper	139, 189	9, 12
Size of plan	140	9
Plans may be required to be drawn for photo-lithography	141	10
Number of portions on a plan	142	10
Plans not to be folded	143	10
Bearings of magnetic meridian to be shewn on plan	145	10
Plan to have north point upwards	146	10
Magnetic north and magnetic variation to be shewn on plan	147	10
Scale to be drawn on plan of extensive survey	148	10
Sould to be drawn on plan of extensive survey	170	10

Subject.	Paragraph.	Page.
Scale for town allotments on plan	149	10
Scale for plans of suburban portions	150	10
Scale for plans of country portions	151	10
Scale for plans of leases	152	10
Scale for plans of feature surveys	154	10
Of boundaries of portions	155	10
Bearings of portions, to be recorded in degrees and minutes	156	10
Of traverse lines	157	10
Plans of portions to be tinted and edged	158	10
List of colours to be used on plans	159	10
Bearings to be shewn in blue broken lines	160	11
Red writing prohibited except for road and alignment plans	161	11
Connections to be written on plan	162	11
Physical features to be shewn on plan	163	11
Trigonometrical stations to be shewn on plan	163	11
Hills and undulations to be indicated on plan	164	11
Features, improvements and fencing to be shewn on plan	165	11
Reserved roads and tracks to be shewn on plan	166	11
Connections to reserved roads to be given	167	11
Old boundaries as found - to be shewn on plan	168	11
Corners and reference marks to be shewn on plan	169	11
Topographical particulars to be shewn	170	11
Reserve or tenement within a portion to be shewn	171	11
Names of rivers, creeks, &c., to be written on plan	172	11
Plans of feature surveys to be in sheets	173	11
Co-ordinate lines on plans of roads or feature surveys to be in blue	174	11
Parish No. and area to be shewn on plan	175	11
Boundaries of Counties, Parishes, &c., to be shewn on plan		
[Appendix U]	176	11
Fractional quantities to be omitted from plans	177	11
Reference to corners to be noted on plan in tabular form	178	12
Title of plan not to be abbreviated	179	12
Applicant's name to be written in full on plan under the title	180	12
Title of plan of survey for a special purpose	181	12
Notes on plan required	182	12
The term" lot" not to be used on plan	183	12
Date of completion of survey to be given on plan	185	12
Driftways - Payment for survey of	229	16
Enclosures - Severed by a road to be shewn on plan	198	13
Encroachment - On measured portions	61	4
Envelopes - To be addressed O.H.M.S., &c.	207	14
Equipment - Required to be provided by a surveyor [Appendix A]	4	1
Erasures - not to be made in field notes	24	2
Erroneous Surveys -		
May be rejected and cost disallowed	11	1
May lead to cessation of employment and stoppage of advances	15	2
Errors in surveys -		
To be reported to District Surveyor with sketch	67	4
Limits of, allowable	67, 68	4, 5
Feature surveys -	•	•
•		

Subject.	Paragraph.	Page.
Bearings required to distant objects	83	6
Connections to County and other marked boundaries	84	6
Traverse to follow features to be surveyed	85	6
Offsets not to exceed 150 links	85	6
Selection of features for connection survey	86	6
Connections to be as direct as possible	86	6
Marking of [Appendix T]	120	8
Method of indicating special marks on plan	135	9
Scale of plans of	154	10
Plans to be drawn in sheets	173	11
Co-ordinate lines to be shewn on plans	174	11
Reports on, to give physical conditions of country	214	14
Rate of payment for	226	16
Fencing-	220	10
-	36	2
Boundaries exempted from, to be noted in field notes	36	$\frac{2}{2}$
Boundaries that will admit of give and take fences to be shewn		
Return of, to accompany road plans. [Appendix L]	196	13
Reports on exemptions	217	14
Field notes-	10	2
To be recorded on sheets supplied by the Department	18	2
Not to be cut	18	2
Class of survey to be recorded at beginning of notes	19	2
Certificate to be at end of notes	19	2
To be forwarded to District Surveyor with each survey	20	2
Te be precise and complete	21	2
Diagram to be provided in notes to illustrate survey	22	2
To be original notes, not merely copies	23	2
To be recorded in ink	23	2
Erasures not to be made	24	2
Date of Survey, applicant's name, &c., to be given	25	2
Initial line of survey and azimuth to be shewn	26	2
Bearings to be shewn and repetition of angles	27	2
Lengths to be entered as read	28	2
Corrections for hypothenusal measurements and temperatures	28	2
Closing angle to be observed and noted	29	2
Reference to corner trees - Method of shewing	30	2
Features to be shewn comprehensively	31	2
Intersections of features, fences, &c., on measured lines to be shewn	32	2
Lines re-chained to be specified	32	2
Position and state of old marks to be given	32	2
Intersections, offsets and width of watercourses to be shewn	33	2
Position of improvements, ownership and, value to be noted	34	2
Full particulars as to Water Supply to be given	35	2
Character of soil and timber to be given	35	2
Grazing or agricultural capabilities, &c., to be noted	35	2
Geological formation of country to be given	35	2
To note what boundaries may be exempted from fencing	36	2
To note boundaries that will admit of give and take fences	36	2
Capital and rental values of land to be noted	37	2
Fine -	51	_

Subject.	Paragraph.	Page.
May be imposed for faulty survey	13	1
Not to exceed 25 per cent. on authorised charges	13	1
Fords and Crossings - Roads to be of extra width at	48	3
Forests - Limits of to be shewn on plans	165	11
Fractions of inches and links - To be omitted from plan	177	11, 12
Frontage -	1//	11, 12
To Watercourse - Survey of portion with	39	3
Any doubt as to - To be referred to District Surveyor.	40	3
	220	15
Gates (Public) - Report on to give full particulars	220	13
Geological formation -	25	2
To be stated in field notes	35	2
To be recorded on plan	170	11
Gold Fields-	4 70	4.0
Boundaries of, to be-shewn on plan in yellow	159	10
Report on surveys on	216	14
Government survey mark - Destruction of. [Appendix F]	137	9
Grazing capabilities -To be stated in field notes	35	2
High Water Mark - Directions for determining. [Appendix C]	56	4
Hills - To be shewn on plans	164, 172	11
Homestead farms - General directions for survey	75	5
Homestead Selections. General directions for survey	75	5
Improvements -		
Particulars of - to be given in field notes	34	2
Position and extent of, to be shewn on plan	165	11
Particulars of, to be given in reports	213	14
Improvement purchases -	213	1.
Form of measurement and area of	73	5
Any modification to be submitted to District Surveyor	73	5
Inaccessible boundaries - Method of dealing with	42	3
Instructions -	72	3
Officers authorised to issue	2	1
		1
To be carried out in order of sequence	5	1
To be acted on promptly	5	1
To be withdrawn from Surveyor if delayed	5	1
Instruments-		
Required by a, surveyor. [Appendix A]	4	1
Theodolite to be used unless otherwise directed	7	1
To be subject to approval of District Surveyor	7	
Intersections - To be shewn in field notes	33	2
Isolated portions - Bearing to be observed from	66	4
Lagoons - Measurement of portions fronting	55	4
Lakes -		
Measurement of portions fronting	55	4
Names of, to be written on plans	172	11
Lanes - Width of	38	3
Landing places - Roads to be of extra width at	48	3
Latitude and Departure - Survey to be tested by	68	5
Leases -		-
For mining purposes	60	4
General directions for survey of certain classes of	76	5
Company of the control of the contro	, 0	2

Subject.	Paragraph.	Page.
Lines previously marked by same surveyor - Payment for	232	16
Local Increase - Payment of	240	16
Lockspits –		
Dimensions of	103	7
At stakes on road surveys	122	8
Magnetic north - To be shewn on every plan	147	10
Magnetic variation -		
Determination of	53	4
Payment for determining	234	16
Marking - To be effaced when survey is rejected	12	1
Marking (General) -		
To be done in a permanent manner	96	7
Stakes, posts, lengths and description of	96	7
Of reference trees or rocks - Method of. [Appendix T]	97	7
Subdivision line on measured portion	98	7
Of reference trees - Bearings, &c., to be observed	99	7
Of corner reference trees of portions	100	7
Post to be used if tree not available	102	7
Lockspits, direction stakes, &c. [Appendix T]	103	7
Use of broad arrow	104	7
By peg or stake on track in use	105	7
Of boundaries, corners, alignment, &c.	106	7
Marking (Town and Suburban portions) -	100	,
	107	7
Clearing of boundary lines	107	
Trees along and within 3 feet of boundary lines	108	7
Section corner. [Appendix T]		7
Allotment corner. [Appendix T]	110	7
Rock at comer. [Appendix T]	111	8
Suburban portions and numbering of	112	8
Marking (Country portions) –	110	0
Clearing of boundary lines	113	8
Trees on or near boundaries. [Appendix T]	114	8
Rock on boundary at corner. [Appendix T]	117	8
Renewing marking of a common boundary	118	8
Marking (Reserves) - Reference marks to bear inscribed significant letters.		
[Appendix T]	119	8
Marking (Feature Survey) -		
Special marks to be inserted. [Appendix T]	120	8
Bearings and distances to be recorded to tree or post. [Appendix T]	120	8
	120	8
Copper tacks on apex of broad arrow. [Appendix T]	120	8
Marking (County Boundaries) - Reference marks to bear initial letters of		
counties. [Appendix T]	121	8
Marking (Roads) -		
To be defined on both sides	122	8
Miles to be marked On trees or post	123	8
Corner posts to bear broad arrow over letters RD. [Appendix T]	124	8
Of reserved road through a portion	125	8
Marks (Special) -		
To be inserted at reference points on feature surveys. [Appendix T]	120	8

Subject.	Paragraph.	Page.
To be capable of identification	126	9
Copper plug, iron tube or bottle to be used	127	9
Description of copper plug	128	9
Mode of fixing plug	129	9
Description of bottle mark and fixing of same	130	9
Description of iron tube mark and fixing of same	131	9
Position in road surveys	132	9
In country portions	133	9
In feature surveys	134	9
To be indicated on plans	135	9
Only to be inserted under direction of District Surveyor	136	9
Payment for	235	16
Measured Portions –	233	10
Subdivision of	61	4
Connections required	62	4
Memoranda - Must meet with immediate attention	14	2
Meridian - As to adoption of	41	3
Milage rate - For travelling with camp and equipment	236	16
	60	4
Mining - Lands leased for purposes of	45	3
Miners' Rights not to be marked in Crown leases	8	
Monthly Progress Report - To be furnished	_	1
Municipal boundaries - To be shewn on plans	176	11
Municipal Council - To be informed of road surveys	78	5
Needle (Magnetic) - To be kept in correct adjustment	41	3
North Point - To be upwards on plans	146	10
Obliteration of corner marking - Cancelled portions	224	16
Observations - Solar or stellar for magnetic variation. [Appendix B] Offsets -	53	4
Not to exceed certain limits	85	6
To be shewn in field notes	33	2
Old, boundaries - As found, to be shewn on plans	168	11
Old reference marks - To be shewn on plans as found	169	11
Old Marks - Particulars of to be given in field notes	32	2
Owner or occupier - alienated lands - to be notified by Surveyor before		
entry on	16	2
Paper - Corners not to be turned up	204	13
Payment -		
For boundaries measured and marked	222	15
Corners (new and other)	223	15
Feature surveys, ranges, watercourses, &c	226	16
Connections	227, 231	16
For survey of roads 3 chains in width and cosecants	228	16
For survey of roads over 3 chains in width and cosecants	229	16
For survey at roads under Public Roads Act and cosecants	230	16
Subdivision of measured portion	231	16
Lines previously measured by same surveyor	232	16
Comparison of azimuth	233	16
Determination of magnetic meridian	234	16
Special marks	235	16
Travelling with camp and equipment	236	16

	Subject.	Paragraph.	Page.
	Of survey fees exemplified Diagrams Ia, b, c	237	16
	For report on Form L.L.B. 78	239	16
	Of district increase	240	16
	For surveys by Special contract	241	16
	By daily rates	242	16
Plans -			
	May be rejected for defective drawing, &c	12, 144	1, 10
	When rejected payment not to be allowed	12	1
	Magnetic variation to be shewn on. [Appendix B]	53	
	Bearings to trigonometrical stations to be recorded on	63	4
	To shew starting point and prominent features	70	5
	Scale of, for trigonometrical connections	94	6
	Position of special marks to be indicated on	135	9
	To be of best mounted hand made drawing paper	139	9
	Size of	140	9
	May be required to be drawn for photo-lithography	141	10
	Number of portions to be shewn on	142	10
	Not to be folded	143	10
	Bearings to magnetic meridian to be given	145	10
	To have north point upwards	146	10
	Magnetic north and magnetic variation to be shewn	147	10
	Scale, for extensive surveys	148	10
	Scale, for town allotments	149	10
	Scale, for suburban portions	150	10
	Scale, for country portions	151	10
	Scale, for leases	152	10
	Scale, for feature surveys	154	10
	Method of indicating bearings on	156	10
	Method of indicating traverse lines on	157	10
	Of portions to be tinted and edged	158	10
	Colours to be used on	159	10
	Method of indicating lines not chained	160	11
	Red writing not to be used on, except for road traverses and		
	alignments	161	11
	Connection to be written on	162	11
	Physical features to be shewn on	163	11
	Trigonometrical stations to be indicated on	163	11
	Hills and undulations to be shewn	164	11
	Features, improvements, and fences to be shewn	165	11
	Reserved roads and tracks to be shewn	166	11
	Connections to roads to be given on	167	11
	Old boundaries to be shewn on, as they are found	168	11
	Corners and reference marks to be indicated as they are found	169	11
	Topographical information to be given on	170	11
	Reserve or tenement within a portion to be shewn	171	11
	Rivers, lakes, &c., Names of, to be written on	172	11
	Feature Survey - To be in sheets	173	11
	Feature and road surveys - co-ordinate lines to be shewn	174	11
	Area and Parish Number of portion to be given	175	11
	Distinguishing boundaries to be shewn [Appendix U]	176	11

Subject.	Paragraph.	Page.
Fractional quantities, to be omitted	177	11, 12
Reference to corners, to be in tabular form	178	12
Abbreviations not to be used in title	179	12
Names of applicant to be written in full under title	180	12
Surveys for special purposes - Title of	181	12
Particulars of situation of land to be given	182	12
The term "lot" not to be used on	183	12
Date of survey to be given on	185	12
To be transmitted as soon as possible after survey	186	12
Of amended surveys to be accompanied by letter	187	12
To be sent in with letters	188	12
Specimens, illustrating instructions, [Appendices Za, b, R, S]	200	13
Plug - For special marks	128	9
Portion - Definition of term	128	1
Portions -	1	1
	20, 40	2
Fronting watercourse - Measurement of	39, 40	3
Road must be provided to	44	3
Roads to form boundaries as far as possible	47	3
Fronting lakes, lagoons, and swamps - Measurement of	56 5.5	4
Fronting tidal waters - Measurement of	55	4
Numbering of	57	4
To be connected with some previous survey	58, 65	4
Measured - Subdivision of	61	4
Marking reserved road through	125	8
Number of, to be shewn on plan	142	10
Portions (Suburban) – Scale for plans of	150	10
Portions (Country) - Scale for plans of	151	10
Posts for marking surveys	96, 102	6, 7
Progress Report to be furnished monthly. [Appendix K]	8	1
Public Gates - Reports on, to give full information	220	15
Quarries - Reservations for	49	3
Ranges -		
Summits of, to be shewn in field notes	32	2
Rate of payment for survey of	226	16
Reference Marks - Particulars to be given on plan	169	11
Reference stations - Marking of country portions	115	8
Reference trees - Marking of country portions. [Appendix T]	9	7
Regulations -	2	1
Officers authorised to issue instructions under	2	1
Non-compliance with - Penalties for	15	2
All questions under, to be decided by the Surveyor-General	17	2
Appendices to be part of	256	17
Reference to District Surveyor in cases not provided for in	257	17
Real Property Surveys		
Plan to be on approved form, [Appendix Z]	153	10
Tracing being an exact copy of plan, to be furnished	153	10
Area to be quoted to nearest perch	177	11, 12
Certificate to be furnished. [Appendix Q]	153, 184	10, 12
Payment for tracing of plan	238	16
Account for tracing, to be on Form A	246	17

Subject.	Paragraph.	Page.
Re-marking - Common boundary of previously defined portions	118	8
Rental value of land to be given in field notes	37	2
Reports -		
To be transmitted to District Surveyor	3	1
General information required	212	14
Full particulars of improvements to be supplied	213	14
On feature surveys - Conditions of country to be stated	214	14
To be furnished on approved printed form when so directed	215	14
On portions measured on a gold or mineral field	216	14
On fencing exemptions	217	14
On approved printed forms - Payment for	239	16
Reserve within a portion to be shewn on plan	171	11
Reserves -		
For water supply, &c., to be provided	49, 71	3, 5
For water races	51	3
Marking of. [Appendix T]	119	8
To be indicated on plan by emerald green	159	10
Boundaries of, to be shewn on plans. [Appendix U]	176	11
Reports on, to be comprehensive	218	14
Ring barking - Position of to be shewn on plan	165	11
River -		
Separating portions, connection required	64	4
Position of, to be shewn on plan	163	11
Bearing to opposite side, to be noted on plan	160	11
Name of, to be written on plan	172	11
Roads - To be provided in suitable positions	44, 46	3
To be provided in suitable positions	44	3
Must be provided to every portion	44	
To form boundaries of portions as far as possible	47	3
When reserved, to be marked on both sides	47	3
To be of extra width at fords and crossings	48	3
Reservation for, out of conditional purchases	71	5
Surveys to be carried out under Acts and Regulations	77	5
Shire and Municipal Council, to be informed of survey of	78	5
Intersection of, marked boundaries to be noted	79	5
Connections to be made to measured portions	79	5
Position of dwelling-house within 200 yards to be given	79	5
Need not be uniform in width	80	5
Marking of	122-125	8
Position of special marks to be indicated	132	9
Reserved, to be indicated on plan by burnt sienna	159	10
Through portions to be indicated on plan	166	11
Intersecting boundaries, connections to be shewn on plan	167	11
Co-ordinate lines to be shewn on plan	174	11
Best mounted drawing paper to be used for plans	189	12
Plans to be plotted longitudinally on the paper	190	12
Scale for plans and diagrams	191	13
Colours to be used on plans	192, 193	13
Writing on plans to be black, except as prescribed in certain cases	194	13

Subject.	Paragraph.	Page.
Title of plan of. [Appendix R]	195	13
Schedule and return of fencing to accompany plan. [Appendix L]	196	13
Plan and return to be signed by Surveyor	197	13
Enclosure severed to be indicated on plan	198	13
Letter reporting survey to give full particulars	199	13
Reports on - To state public requirements, &c	219	15
Payment for survey of	228,229,230	16
Rocks -	,,	
At corner - Marking of, for town and suburban portions.		
[Appendix T]	111	8
At corner - Marking of, in country portions. [Appendix T]	117	8
To fix special mark in	127,128,129	9
Rock Marks, to be preferred in any survey	134	9
Schedule of Prices -		
Application of. [Appendices Ia, Ib, Ic]	222-235	15, 16
School Sites to be shewn in blue on plan	159	10
Section corner - Marking of. [Appendix T]	109	7
Shire Council to be informed of road surveys	78	5
Special contract - Surveys may be let by	241	16
Special Marks -		
To be inserted in feature surveys. [Appendix T]	120	8
(Vide marking)	126-136	9
Payment for	235	16
Specimen plans, illustrating instructions, [Appendices, Z, Za, Zb, R, S]	200	13
Standard - Steel or invar band to be kept by Surveyor as a	7	1
Streets -		
Not to be less than 100 links wide, generally 150 links	38	3
Alignment of. [Appendix D]	81	5
Subdivisions -		
of measured portions	61, 98	4, 7
Payment for	231	16
Suburban holdings - General directions for survey of	75	5
Suburban Portions -		
Area not to exceed 20 acres	38	3
Offsets not to exceed 75 links	59	4
Marking and numbering of	112	8
Surcharges -		
May be recovered as a debt from Surveyor in default	11	1
Not to exceed charges for original survey	11	1
Of cost of inquiry or amendment of survey	14	2
Survey -		
Definition of term	1	1
To be to standard measurement of the Department	7	1
Proposed modification, to be reported to District Surveyor	72	5
Date of, to be given in field notes	25	2
Initial line and azimuth to be clearly indicated in field notes	26	2
Must be performed under Regulations	2	1
If erroneous may be rejected	11	1
If faulty, fine may be imposed	13	1
If erroneous or incomplete may lead to cessation of employment	15	2

Subject.	Paragraph.	Page.
Magnetic variation to be determined. [Appendix B]	53	4
Near trigonometrical station, bearings to be observed	63	4
Of isolated portions	66	4
Limit of error allowed in	67, 58	4, 5
Use of broad arrow	104	7
For special purpose - Particulars to be given on plan	181	12
Plans to be sent in as soon as possible after	186	12
Mode of remuneration for	221	15
Surveyor-General –		
Definition of term	1	1
Authority to issue instructions	2	1
Decision of, on questions under Regulations to be final	<u>-</u> 17	2
Surveyor -	17	_
Definition of term	1	1
To provide himself with equipment. [Appendix A]	4	1
To obtain necessary Acts of Parliament, &c	4	1
Not to employ a deputy	6	1
To keep a steel or invar band as a standard	7	1
To furnish progress report monthly. [Appendix K]	8	1
To notify District Surveyor of proposed absence from district	9	1
Not to apply for land unless sanctioned by Minister	10	1
To give immediate attention to memoranda re errors or omissions.	14	2
To notify owner or occupier of alienated land before entry on	16	2
To report destruction of survey marks	137, 138	9
To be allowed mileage rate whilst travelling with camp	236	9 16
To have bank account	230 247	17
To be informed of alterations in accounts	254 254	17
	234	1 /
Swamps - Massurament of partians fronting	55	4
Measurement of portions fronting To be shewn on plans		4 11
±	165	
Tenement within a portion to be shewn on plan	171	11
Territorial Surveys - Scale for plans of	154 56	10
Tidal waters - Measurement of lands fronting. [Appendix C]	56	4
Topographical surveys - Directions for carrying out. [Appendices P, P ¹]	87	6
Town allotments -	20	2
Not to exceed ½ acre, on proclaimed gold or mineral field ¼ acre	38	3
Marking of. [Appendix T]	107-111	7, 8
Accounts for survey of, to be subject to 10 per cent. Decrease	225	16
Scale for plotting	149	10
Town sections - Payment for marking of corners	223	15, 16
Tracks to be indicated on road plans	166, 193	11, 13
Travelling - With camp and equipment - Allowance for	236	16
Traverse -	70	4
Offsets from lines of	59	4
For feature surveys	85	6
Method of indicating lines on plan	157	10
Trigonometrical connections -	0.5	_
To be traversed as directed in instructions	88	6
Bearings to be determined by included angles	89	6
To a portion, one side to be re-traced	90	6

Subject.	Paragraph.	Page.
Bearings of circumjacent trigonometrical stations to be observed Formula for determining differences of azimuth with	91	6
trigonometrical survey	92	6
Base of triangle may be used	93	6
Plan to be 20 chains to an inch	94	6
Trigonometrical stations -		
Sites to be reserved for	50, 71	3, 5
Bearings to be observed to	63	4
Position of, to be shewn on plans	163	11
Tube mark - To prepare, for special marking	131	9
Watercourses -		
To be noted in field notes	33	2
Survey of portions fronting	39, 55	3, 4
To be indicated on plans	163	11
Remuneration for survey of	22	16
Water races - Reserves for	51	3
Water supply - Reserves for	49, 71	3, 5
Wharves - Reserves for sites for	49	3

LIST OF APPENDICES

Appendix	Subject	Page
A	Instruments required by a Surveyor	19
В	Observations for Latitude and Meridian	
C	Determination of Mean High Water and the Rise and Fall of the Tide	19-20
D	Instructions for Alignment of Streets	
E	Instructions for Survey of a General Cemetery	20-21
F	Protection of Government Survey Marks	21
G	Form for Computation of Areas	21
Н	Report Form L.L.B. 78	22
Ia	Account Form, with Diagram - C.P., C.L., or Aln.	23-27
Ib	Account form with Diagram - Town Allotments	28-32
Ic	Account Form, with Diagram - Subdivision of Measured Portions	33-37
Id	Account Form B - Specimen Copy	38-39
J	Authorised Abbreviation of Words on Maps	40
K	Form of Monthly Progress Journal	41
L	Form for Return of Fencing	42
M	Schedule of Proposed Resumptions - Public Roads Act, 1902	43
N	Schedule of proposed resumptions and Withdrawls and Roads to be Closed	44-45
O	Permission of Owner to Resumption of Land for Road	46
P, P1	Directions for Topographical Surveys with Specimen Plan	46-47
Q	Certificate of Survey of land under Real Property Act	47
R	Specimen Plan - Road Survey	49
S	Specimen Plan and Diagram - Alignment Surveys	50
T	Diagrams Illustrating Marking	51
U	Diagram showing Distinguishing Boundaries	52
V	List of Letters Significant of Holdings and Reserves	53
Wa	Specimen Letter Form - Conditional Purchase	54
Wb	Specimen Letter Form – Alienation	55
Wc	Specimen Letter Form - Conditional Lease	56-57
Wd	Specimen Letter Form - Improvement Purchase	58-59
We	Specimen Letter Form - Report on Improvement Purchase	60-61
X	Designs for General Cemeteries	62
Y	Specimen Plan of Portion Survey	63
Z	Specimen Plan for Real Property Act Survey	64
Za	Specimen Plan of Connection Survey	65
Zb	Specimen Plan of Country Portions	66

1914

NEW SOUTH WALES.

Regulations for the Employment of Surveyors by The Department of Lands.

1. In these Regulations the word "Surveyor" shall mean any person duly licensed as a surveyor of the State of New South Wales, The expressions "Surveyor General" and "District Surveyor" shall mean irrespectively those officers of the Department of Lands. The word "portion" shall mean an area of land measured under authority and numbered as of a parish. The term "survey" shall include, beside measurement and marking, the drawing of the plan, preparation of the letter transmitting same and of reports and schedules on approved forms

Preliminary

2. All surveys and duties shall be performed under these Regulations, upon instructions issued by the Surveyor-General, or a District Surveyor, or an officer specially authorised by the Surveyor-General.

Officers authorised to issue instructions.

3. All official correspondence, reports, plans, and accounts shall be transmitted to the District Surveyor.

All Communication to be sent to the District Surveyor.

4. A Surveyor shall provide for himself the surveying instruments mentioned in *Appendix* A; also the necessary equipment and labour, copies of plans of adjacent surveys, Acts of Parliament, and all other information requisite for the proper performance of the service entrusted to him.

Equipment.

5. All Instructions shall be acted on prompt1y, and as far as practicable in due order of sequence; neglect in this respect may lead to stoppage of advances on account, or withdrawal of instructions.

Prompt attention requisite.

6. Measurement by deputy, signing the decl aration on plan or account in cases where survey or amendment of survey or inspection has not been performed by the Surveyor duly authorised or accepting other remuneration than payment by the Department for Services performed under these Regulations, are strictly prohibited, and will lead to cessation of employment of the Surveyor thus offending.

Measurement by deputy prohibited.

7. A theodolite with not less than 5-inch plates shall be used in all surveys, unless the District Surveyor authorizes in writing the use of some other instrument. All instruments shall be subject to the approval of the District Surveyor. All measurements of length shall be subject to the standard kept by the Lands Department of New South Wales. Every Surveyor shall keep a steel or invar band to be used solely as a standard and it shall be tested at such times as the District Surveyor may direct.

Theodolite to be used unless another instrument be authorised.

Standard band to be kept.

Monthly Progress

Report.

8. The Surveyor shall for each calendar month compile a progress report on the approved form, and shall transmit the same to the District Surveyor under whom he may be employed on or before the third day of the following month. *Appendix* K

9. Sufficient notice of any proposed absence from district, its probable duration, and the Surveyor's address during period of absence are to be given to the District Surveyor, so that approval or otherwise may be intermated. Neglect in this respect will jeopardise further employment.

Absence from District.

10. The employment of a Surveyor is held to preclude him from applying for any holding under the Crown Lands Acts, unless with the sanction of the Minister.

Applications for land by Surveyor.

11. Surveys found to be erroneous, or surveys in contravention of. the Land Acts, or surveys not in accordance with these Regulations, may be rejected by the Surveyors General or District Surveyor, and the charges for the same may be disallowed; or, if such charges have been paid, the amount thereof may be surcharged against any moneys which may be due or may become due, or may be recovered as a debt from the Surveyor in default; or, if another Surveyor be employed to amend or remeasure, then the cost of his services (but not exceeding the charges for the original survey)" may be surcharged to the account of the Surveyor in default, or may be recovered from him as a debt.

Erroneous survey may be rejected, and charges disallowed, or cost of amendment surcharged.

12. When survey is rejected for any of the before-mentioned causes, the marking shall be effaced by the Surveyor in default if so directed. A plan may be rejected, on account of erroneous survey, defective drawing, or other sufficient reason. A rejected plan will not be returned to the Surveyor, neither shall payment for the same be allowed.

Marking to be effaced, Plan not to be returned.

13. Under certain circumstances, e.g., when there has been failure to complete a survey in accordance with these Regulations, or when a plan has been inaccurately or badly drawn, or an area has been incorrectly computed, and it may not be expedient to reject the survey or plan, a discount, to be approved by the Minister, which shall not exceed 25 per cent. on the authorised charges for the service, may be imposed to cover the cost of professional labour involved in examination and amendment; or, in event of the charges for the imperfect service having been paid, such discount may be surcharged to the account of the Surveyor in default or may be recovered from him as a debt.

Fine may be imposed for faulty service.

14. Memorandum *re* errors or omissions in connection with any service must meet with immediate attention and reply by the Surveyor; if unanswered for a period exceeding one month it shall be competent for the Surveyor-General or District Surveyor to cause inquiry or amendment of survey, the cost of which may be surcharged to the Surveyor's account

Memorandum *re* defects.

15. Erroneous or incomplete surveys or failure to comply with these Regulations shall be held to be a sufficient cause for cessation of employment of the Surveyor or the stoppage of advances on accounts.

Unsatisfactory service will lead to cessation of employment or stoppage of advances.

16. Attention is directed to the propriety of giving reasonable notice to the owner or occupier of alienated land before entry thereon in connection with any survey under these regulations.

Entry on alienated lands.

17. The decision of the Surveyor General on all questions arising under these Regulations or in connection with the practice of the Department shall be final.

Practice to be decided by the Surveyor-General.

SURVEY AND MEASUREMENT FIELD-NOTES OF SURVEY.

18. Field-notes shall be recorded on standard double sheets of paper supplied by the Department. The sheets are not to be cut.

Field-notes.

19. Class of survey and particulars thereof must be recorded at the beginning of the field-notes, and the date of completion, together with a certificate in the following terms must be entered at the end of the field-notes and subscribed by: the Surveyor:—

This is to certify that the field-notes herein contained are the actual results of my observations and measurements in the field.

Licensed Surveyor.

- 20. The field-notes of each survey shall be sent to the District Surveyor with the plan, &c., to which they refer.
- 21. As the field-notes are the primary record of survey, are accepted as evidence in a Court of Law, and are for Departmental reference, it is of importance that they should be precise and complete, and kept in a neat and professional manner
- 22. A diagram shall be provided in field-notes to illustrate same.
- 23. Field-notes shall contain the notes actually taken in the field, not copies merely and it is desirable that they shall be recorded in ink
- 24. In the event of alteration of a mistake, there should be no erasure, but the erroneous entry should be neatly struck through, and the correction written above.
- 25. Date of survey, portion No., parish, county, applicant's name, and purpose of survey; registration Nos. (e.g., for conditional purchase, homestead lease, special lease &c), shall be first entered in each case; and the number and date of letter transmitting plan shall be added in due course.
- 26. The initial line of every survey and azimuth adopted shall be clearly indicated.
- 27. Bearings shall be clearly shewn with particulars of repetition of angles.
- 28. Length shall be entered as read, corrections for hypothenusal measurement and temperature shall be noted, and the lengths deduced therefrom shall be distinctly indicated.
- 29. Whenever there may be a close, in the measurement of an area, or in a feature survey, or road survey the closing angle shall be observed and noted.
- 30. References to corner tree may either be shewn on a diagram or in tabular form referred to in diagram by alphabetical letters.
- 31. Features shall be shewn comprehensively, so that a draftsman may be enabled to represent the general aspect of the country.
- 32. On measured lines, the intersections of watercourses, summits of ranges, other natural features, fences, &c &c shall be correctly noted; lines rechained shall be so specified. Position and state of preservation of old marks shall be carefully noted
- 33. Intersections, offsets, and widths of watercourses shall be shewn in the traverse of features. It is not sufficient to draw them without noting distances
- 34. The positions of improvements shall be clearly indicated; particulars of ownership, description, and value shall be entered, and also the dates when the improvements were effected.
- 35. Full particulars shall be stated as to the character of soil and timber, grazing or agricultural capabilities, water supply, and the geological formation of the country.
- 36. The Surveyor shall take such notes whilst in the field as will enable him in his letter transmitting the plan to report precisely in any case what natural boundaries or parts thereof might be exempted from the condition of fencing, or admit of give-and-take fence.
- 37. Notes shall be made of the estimated capital and rental values of land. These may be especially useful to the surveyor when called upon to give evidence in Court.

TOWN AND SUBURBAN LANDS.

38. Town allotments shall not exceed ½ acre each, and on a proclaimed Gold or Mineral Field ¼ acre. Streets shall not be less than 100 links wide, and as a general rule shall be 150 links. Lanes shall not be less than 20 feet wide, and as a general rule shall be 31 links. A suburban portion, when measured for auction sale, shall not exceed 20 acres.

Town Allotments – area of.
Width of streets,
Widths of lanes,
Suburban portions – areas.

COUNTRY LANDS.

39. In the measurement of a portion fronting a watercourse, the boundary of the area shall be as nearly as practicable the fair limit of the channel, excluding from the area shingle beds and all lands embraced within the ordinary bed of the watercourse. When the bank at a corner is liable to erosion the corner stake should be placed on the boundary a short distance back from the bank, but in such a case the distance therefrom to the fair limit of the channel shall be stated.

Fronting water courses.

40. Where there is doubt as to whether a portion should be measured with frontage, reference should be made to the District Surveyor, upon whose instructions survey shall proceed.

Frontage – doubt as to what may constitute.

41. The principle laid down in the Crown Lands Act in reference to conditional purchases that all such measurements having boundaries other than frontages shall be directed to the cardinal points shall be followed as far as practicable. A Surveyor must therefore keep the magnetic needle of the instrument in correct adjustment. Where a new measurement adjoins an older measurement, the meridian of the latter shall he adopted where the magnetic readings differ less than 30 minutes, unless the District Surveyor directs the adoption of the meridian of an adjacent survey, or a meridian stated relatively to the true north.

Direction of boundaries to cardinal points.

42. Where part of a boundary, or parts of boundaries, may be inaccessible, a connecting traverse is to be made between the extremities of the measured parts, and at such extremities stakes are to be inserted, and their positions determined relatively to reference trees marked with the broad-arrow. The unmeasured parts shall be delineated upon the plan by broken lines.

Inaccessible boundary.

43. Where there is a cliff which forms a natural barrier, the boundary of the portion shall be defined by right lines approximately following the cliff.

Cliff forming a natural barrier.

44. For the purposes of intercommunication or access to water supply, roads shall be provided in the most suitable positions: Such roads may be of various widths, according to the conditions of the ground and the circumstances of traffic, and shall not be less than 100 nor more than 300 links wide, unless otherwise directed. A road must be provided to every portion or member of a series of a holding, or where necessary to any reservation or authorised mining occupation with the exception mentioned in the next succeeding paragraph.

Roads for intercommunication.

45. In the measurement of a Crown Lease the surveyor marking or boundaries of any lands occupied under Miners Rights is not required, nor are access roads to be specially provided. The approximate positions of such occupations are to be indicated on plan; particulars afforded and areas excluded from the area of the Crown Lease.

Miners Rights within Crown Leases.

46. As a rule, a diagram showing the figure of the area to be measured will be annexed to the instruction. Upon this diagram roads for reservation may be delineated, but such are to be regarded merely as indicating probable local requirements. The Surveyor shall select the most suitable positions for roads.

Form of measurement.

47. As far as possible, roads should form boundaries of portions to be measured, i.e., an area may be modified in form so that the road in the most desirable position shall be a boundary; where the reservation of a road through a portion may be unavoidable the Surveyor shall survey and mark the same on both sides, unless otherwise directed. [See paragraphs 122, 125.]

Reservation of a road.

48. At the crossing of a river, creek, or gully, the road shall be provided of suchextra width as may be requisite to enable the formation of the best causeway, or construction of a bridge in the best position. (Especial care should be taken in this matter, where a ford is liable to alteration of site by flood.) This rule will also apply to providing ample and convenient access to water, or to landing-places on navigable rivers.

Roads at fords and crossings.

49. In the subdivision of land, in view of future settlement, the Surveyor should exercise judgment in selecting and recommending for reservation, permanent waterholes, springs, and parts of watercourses desirable for water supply, which may be necessary for the beneficial occupation of the surrounding country; also sites for quarries, wharves, and other public purposes, with sufficient access thereto.

Water supply &c, - Reservation for.

50. The Surveyor shall recommend for reservation suitable areas covering prominent points which may hereafter be useful in the trigonometrical survey of the country, whenever in the course of his duties the necessity for such reservations may present itself; such recommendation to be forwarded to the District Surveyor without delay.

Trigonometrical stations – Sites to be reserved.

51. The position of a water-race intersecting a portion shall be defined by traverse, and there shall be a reservation to a width of 10 feet on each side; where the cutting exceeds 10 feet in depth or a tunnel is constructed the width shall be 20 feet on each side (Regulation 47, Mining Act, 1906).

Water-races to be reserved.

52. All drains legally constructed shall also be traversed unless otherwise directed, in order that reservations may be made to protect same.

Reserves to protect drains.

53. The District Surveyor may require the magnetic variation of the survey to be determined by solar or stellar observations, the particulars of which shall be recorded on the plan, in the approved form. [Appendix B.]

Magnetic variation to be determined.

54. Comparison of azimuth is sometimes needed, e.g., by noting the direction of a boundary intersecting the traverse of a road or other survey, when a connection to a corner is not requisite; or in a connection by traverse to the corner of a portion where the bearing of a boundary should be noted. The latter service is distinct from a connection along a boundary to a corner, which of itself determines azimuth, and will be paid for at connection rates.

Comparison of azimuth.

55. Portions shall not be measured with frontage to lakes, lagoons, ill-defined watercourses, and swamps; the boundaries bordering thereon shall be defined by right lines.

Lakes, lagoons, 7c., - portion bordering on.

56. Land covered by tidal waters cannot be alienated below high-water mark, unless under special conditions as prescribed by law. High-water mark shall be defined as the mean high-tide mark between high-water spring and high-water neap tides. Attention is directed to *Appendix* C. When the conditions are favourable, a road may be provided approximately along high-water mark, to form the boundary of a portion.

Tidal waters – Portion bordering on.

57. All portions shall be numbered as of a parish, and the number to be used will be specified in the instructions for survey.

Parish – numbering portions therein.

58. In order that each portion may be definitely described in a Grant, it is necessary to connect it with some previous survey; where there is no considerable difference in distance, connection shall be made with the nearest measured portion in preference to feature or road surveys. The azimuth of the survey connected with shall be observed and noted on plan.

Connection for description.

59. Offsets from traverse lines to fix the positions of rivers, watercourses, &c., shall not exceed 150 links in surveys of country portions or 75 links in suburban portions.

Offsets.

60. Land under lease or lawful occupation for mining purposes, and lands of which a lease under any Act in force for the time being relating to mining has been applied for, shall not be measured for alienation except on application under section 62 of the Crown Lands Consolidation Act of 1913. Any instruction which cannot be completed for this reason shall be returned as quickly as possible under report. If there be any modification as to form of measurement to avoid interference with mining occupation, full explanation should be afforded in the letter reporting survey.

Land held under Mining Act.

61. No measured allotment or portion shall be subdivided or encroached upon without specific instructions to that effect.

Subdivision of measured portions, and connections.

- 62. In subdivision of a measured portion, connections along boundaries are required from the extremities of the dividing line to the nearest points established in the former survey. The other boundaries of the original portion should be remeasured only when the subdividing line does not *agree* with the original survey close within twice the limit of error allowed by paragraph 68; and such connections and remeasurement shall include remarking.
- 63. In all surveys within view of trigonometrical stations, bearings shall be observed thereto, and the particulars shall be recorded upon the plan.

Bearings to trigonometrical stations to be observed.

- 64. In the measurement of portions separated by a river or creek from other portions, connection shall be made between them at convenient intervals.
- Connections across a water course.
- 65. Whenever a portion is measured within a few chains of any previous survey a connection shall be made to a corner or some other defined point thereof.
- Connection with other marked boundaries.
- 66. When an isolated portion is measured, bearings should be observed from one or more corners or defined points to prominent hills or other conspicuous natural features.

Bearings to distant objects.

67. Where, in the measurement of an adjoining portion, an error which would materially affect the area is found in the former measurement, and where the new measurement if proceeded with would preclude the adjustment of the former measurement, the matter should be immediately referred to the District Surveyor, with a report and sketch in illustration, reference being specially made to existing survey marks, if any, also to fences or other improvements on or near the boundary. For the purposes of this Regulation it shall be held that an error which may require this course of action shall mean an error exceeding one half per centum in length, and indicating an excess or deficiency of area to the extent of one per centum. The following cases are those where an adjustment of area may be considered necessary.

Errors disclosed in measurement.

- (a) In a freehold portion where the error indicates that the area is less than the area stated on the plan.
- (b) In a conditionally-purchased portion where the nominal area of the whole holding is 40 acres, but the error indicates that the area is less than 40 acres.
- (c) In a conditionally-purchased or conditionally-leased portion where the error indicates that the total area of the holding is greater than the maximum area permitted by law.
- (d) In a conditionally-purchased or conditionally-leased portion where the error indicates that the relative legal proportion of areas has been disturbed.
- (e) In a homestead selection, settlement lease, or other lease, where the error indicates that the area is greater than the area stated on the plan
- 68. The accuracy of the survey of each portion shall be tested by latitude and departure, and the close shall be within the following limits of allowable error, viz.:- The sum of the differences of latitude and departure of the perimeter shall not exceed at the rate per mile for boundaries and the parts of boundaries crossing level country 1 link, for undulating country 2 links, and for mountainous country 3 links. The following directions shall apply in deciding the respective classes of country -

Checking closing and allowable error.

"Level," where the slope does not exceed 3 degrees;

"Undulating," where the slope ranges from 3 degrees to 10 degrees;

"Mountainous," where the slope exceeds 10 degrees.

The abrupt banks of watercourses less than 500 links wide shall not be included in estimating the slopes. The Surveyor shall state on the approved form (paragraph 188) the class of country; and if called upon shall shew data in support thereof.

- 69. When instructions have been issued for survey of a specific area, there shall be no deficiency in the area measured.
- Deficiency in area not permitted.
- 70. The marked starting point, and also any prominent feature, &c., referred to in an application for conditional purchase or conditional lease, shall be indicated on the plan from actual measurement, unless the land has been allotted in a modified or different position from that applied for.
- Starting point, features, &c.
- 71. Reserves out of areas conditionally purchased may be made for the purposes specified under section 46 of the Crown Lands Consolidation Act, 1913, viz., for necessary roadways, trignometrical stations, and sites for, and sources of water supply.

Reservation out of area purchased.

72. Any desirable modification of form of measurement shall be reported to the District Surveyor, accompanied by applicant's written consent, if obtainable; but any modification effected without the District Surveyor's approval will be at the risk of the Surveyor.

Modification of form of measurement.

IMPROVEMENT PURCHASES.

73. Within town or suburban limits the form of measurement shall be in accordance with the general design of subdivision; and where modification of the design is found to be desirable, the form of measurement shall be submitted to the District Surveyor.

Form of measurement – town and suburban.

74. The areas to be measured shall not exceed ½ acre for town or village lands as defined by section 3, Mining Act, 1906, and 2 acres for other lands.

Area.

HOMESTEAD SELECTIONS, HOMESTEAD FARMS AND SUBURBAN HOLDINGS.

75. All the general rules herein contained relating to the conducting and marking of surveys shall be generally adopted in the measurement of homestead selections, homestead farms, and suburban holdings unless otherwise directed. A diagram will accompany the instructions, showing the lines to be measured and marked.

General Directions.

LEASES.

76. For survey of boundaries of leases other than conditional leases, conditional purchase leases; and residential leases, special arrangements will be made by the District Surveyor, who will direct what lines are to be measured and marked.

Survey of boundaries of leases.

ROADS UNDER THE PUBLIC ROADS ·ACT.

77. In survey of a road, the provisions of the Acts in force, and Regulations thereunder, must be strictly observed.

Survey of roads.

78. The Shire or Municipal Council must be informed of any surveys of proposed roads or streets, and be asked to instruct its officer to meet and confer with the measuring surveyor on the ground, so that the best position of the road or street may be obtained.

Shire or Municipal Council to be informed

79. The intersection by the road of all marked boundaries shall be noted. Wherever practicable, the bearings of such boundaries shall be determined, and, at suitable intervals on the road traverse, connection measured to a corner or other defined point. Termination of the road survey shall be connected with corners of portions or defined points on other surveys. In an estate severed the position of any dwelling house within 200 yards of the road shall be determined, unless the owner shall have consented to the road. The requisite notes shall be made during survey, to enable the features and improvements to be shewn on the plan as prescribed by Regulations 192 and 196.

Connection with measured portion.

80. The customary width for a road through alienated land is 1 chain, but for sufficient reasons this width may be increased or reduced. It is not necessary that roads shall be of uniform width throughout.

Widths of road.

ALIGNMENT OF STREETS.

81. Survey for alignment of streets shall be performed in accordance with instructions set forth in *Appendices* D and S.

Alignment of Streets.

FEATURE SURVEYS.

82. In a feature survey, observations are required such as shall enable comprehensive representation of the character, etc., of the country.

General Information.

83. As in a feature survey it is desirable to obtain as much information as possible, the surveyor shall observe bearings to determine the position of hills, opposite banks of watercourses, &c.

Bearings to Distant Objects.

84. Intersections of land district, county, run or other boundaries, railway and telegraph lines, &c., shall be carefully noted in the course of survey, and connection to some fixed point thereon shall be made, also with any measured portion within reasonable distance, and where practicable comparison of azimuth shall be noted.

Connections with county and other marked boundaries.

85. Every traverse shall follow as nearly as possible the features to be surveyed, with a view to accurate delineation on plan. Offsets shall not exceed 150 links.

Travers to follow features. Offsets.

86. In selecting features for a connection survey, preference shall be given firstly, to watercourses; secondly, to ranges of hills and divisions of watersheds and lastly to tracks. Where there are no leading features, the connecting survey shall be as direct as possible.

Selection of features for connection survey. Direct connection.

87. Topographical surveys sha11 be made in accordance with special instructions. *See Appendices* P and P¹.

Topographical surveys.

TRIGONOMETRICAL CONNECTIONS.

88. A connection with a trigonometrical station shall be traversed as directed in the instructions, unless found, to be impracticable or very difficult, when the surveyor, may exercise his judgment in selecting another route to or from the same portion or group of portions.

Trigonometrical Survey connection.

- 89. In the connecting traverse, the bearings shall be determined by included angles, to be repeated at least once; and special precaution should be taken to ensure accurate linear measurement.
- 90. When a connection is made to or from a portion, one side shall be retraced as far as may be necessary to accurately determine the azimuth thereof.
- 91. At the station pile the bearings of several of the principal circumjacent trignometrical stations should be observed and the name noted of one or more of them
- 92. In order to determine difference in azimuth from the trigonometrical survey, assuming the connecting traverse to be toward the pile, proceed as follows, viz. :- At the last traverse station x, observe the angle to the mast m and measure the distance; also at x observe the angle to a point y hereinafter mentioned; from m measure a convenient length, say 10 or 20 links to a, point y in the direction of one of the distant trigonometrical piles k, such a one as may be suitable; at y observe the angle subtended by the trignometrical pile k and the traverse station x. These data will enable the angle subtended at m by the points k and x to be computed. The mast or pile should not be disturbed.

- 93. When a trigonometrical pile may be very difficult of access, and a connection by traverse might involve unusually costly service, it may occasionally be desirable if a well conditioned triangle can be obtained to utilise a base, from which the position of the trigonometrical station may be computed, and the azimuths compared.
- 94. The plan shall be drawn to the scale of 20 chains to 1 inch, and in simple style, showing only such boundaries, corners, &c., as are fixed by the connecting traverse, and which can be projected from the field-notes. The features of the country shall be represented as usual. For short connection there is a lithographed plan form, which may be had on requisition.

CEMETRIES.

95. Cemeteries are to be measured and marked in accordance with special instructions as local requirements are found to vary. General directions are afforded in *Appendix* E.

Cemeteries.

MARKING [GENERAL].

96. The following directions shall apply to the marking of all boundaries and all measured areas, excepting those hereinafter specified. The District Surveyor, with the approval of the Surveyor-General, may dispense with any form of marking which is not adapted to any particular locality, and substitute any more suitable marking. All marking shall be performed in a permanent manner, and in accordance with the following specification:-

General Directions.

(a) All stakes shall be of sound, durable hardwood, and shall be split or sawn, as may be directed by the District Surveyor. Stakes at corners, except as prescribed in paragraph 110, and at reference stations, shall be 24 inches long, 4 inches by 4 inches, and 20 inches in the ground. Alignment and direction stakes shall be 18 inches long, not less than 3 inches by 2 inches, and 16 inches in the ground

Stakes.

(b) Reference and corner posts shall be of sound, durable timber, 3 feet 6 inches long, 6 inches square, or 8 inches in diameter, and 24 inches in the ground.

Posts.

In localities where hardwood cannot be obtained, such other timber may be used, and in such form as shall be approved by the District Surveyor.

Timber to be used.

97. Separate reference-trees or rocks shall be marked, when available within 200 links of corners and reference stations, by removing a portion of the bark from the side of the tree facing the stake, and on the surface thus exposed or on the rock inscribing a broad-arrow over the parish number or the characters distinctive of the survey. (*Appendix* T, *diagram* No. 1.)

Reference trees or rocks.

98. In the subdivision of an alienated measured portion for surrender, where part only is to be surrendered, the dividing line shall be marked in accordance with Regulations 113, 114, and 115, but its terminals are to be marked with stakes inscribed with a broad-arrow only and lockspits.

Subdivision of alienated portions.

99. Particulars of all reference trees or rocks, i.e. bearing and distance to the nearest stake of traverse or corner stake, and species of trees and marks thereon, shall be observed and recorded for noting on plan, and such distance shall be horizontal, and the bearing and distance shall be from the broad-arrow to the stake.

Reference trees – particulars of.

100. The number of corners shall as a general rule be restricted to four per portion, and placed at angles indicating the four principal changes in course. Additional corners may be marked in similar positions, not within 20 chains of another corner, but payment for such additional corners will be subject to approval of the District Surveyor.

Numbers of corners to be marked.

101. When a tree stands on a corner, the bark shall be removed from a suitable part facing a boundary line, and on the surface thus exposed shall be inscribed a broadarrow over the parish number or numbers; and if the tree exceeds 16 inches in diameter, it shall be marked by four horseshoe marks, two of which shall be in the alignment of the intersecting boundaries and each distinguished by a broad-arrow. (*Appendix* T, *No.* 9.)

Tree on corner.

102. Where there is no tree or rock available for reference purposes, a post shall be used at the corner, or reference station, having inscribed thereon a broad-arrow over the distinctive letters or numbers of the reference station or corner.

Post where there is no tree.

103. At all stakes, posts, and trees on corners, lockspits, 10 links in length, 1 link in depth and width, and commencing 2 links from the stake, post, or tree, shall be cut, in the directions of the lines of the survey. Where the conditions render it desirable, in lieu of lockspits, stones may be packed in the direction of a boundary, or (excepting in town allotments) direction stakes may be placed 20 links distant from the stake, post, or tree. [See *Appendix* T, diagram *No.*2.]

Lockspits.

Stones may be packed.

Directions stakes.

104. All survey marks, i.e., corner-trees, corner-posts and stakes, alignment-stakes, mile-posts, masts, or beacons (but not blazed trees along boundaries), must be marked with a broad-arrow. For town allotments or small suburban portions, and for alignment stakes, the broad-arrow mark may be punched on the peg. All broad-arrows, letters, and numbers on reference trees and posts shall be of the usual form, and not less than 4 inches in height and ½ inch in depth.

Broad-arrow.

105. When it is requisite to mark a station on a track in use for traffic, by inserting a stake or peg, care should be taken that the top shall be flush with the surface of the ground, and there shall be no lockspits.

Pegs on track in use.

106. All boundary lines, corner, alignment, reference, and terminal points shall be marked and defined as follows:-

TOWN ALLOTMENTS AND SUBURBAN PORTIONS.

107. The building-lines of streets and the side-lines of lanes shall be cleared to a width of not less than 3 feet, by the removal of all scrub and trees of a less diameter than 4 inches.

Clearing boundarylines.

108. All trees along and within 3 feet of a boundary-line shall be marked with the horseshoe mark in the manner prescribed for country portions (paragraph 114).

Trees along boundarylines.

109. Each section corner shall be marked by a split or sawn hardwood stake (paragraph 96) and by lockspits. On a dressed surface of the stake the section number, 3 inches in height, and in ordinary numerals, shall be cut or branded, or painted in black on a white ground, as may be directed; the number of the allotment shall also be marked 2 inches in height, on the section-corner stake. [See Appendix T, diagrams Nos. 3 and 4.]

Section corner.

110. At each allotment corner a split or sawn hardwood stake, 3 inches by 2 inches, and 20 inches long, shall be sunk 16 inches into the ground, and shall be marked with the allotment numbers in figures 2 inches in height. Lockspits shall also be cut at the corners of allotments, 6 links in length, 1 link in width and depth. [See Appendix T, diagram No.5.]

Allotment corner.

111. If a corner shall be on rock, a hole shall be drilled ¾ inch in diameter and 1 inch deep, and a broad-arrow shall be inscribed, and lines shall be marked with a pick in the direction or the boundaries. The section and allotment numbers shall also be cut on the rock. Where the nature of the rock renders it desirable, the broad-arrow, direction lines, and allotment numbers, may be painted. [See Appendix T, diagram No.6.]

Rock at corner.

112. Suburban portions shall be numbered as of the parish and marked in the same manner as country portions; unless where previously designed in sections, when they shall be marked and numbered in the same manner as town allotments.

Numbering Suburban portions.

COUNTRY PORTIONS.

113. All boundary-lines shall be cleared to a width of not less than 3 feet by the removal of all scrub and trees of a less diameter than 4 inches.

Clearing boundarylines.

114. All trees along boundary-lines, within 3 feet in thickly-wooded country and 5 feet in open forest country, shall be marked with the horseshoe mark, which is to be cut into the wood of the tree on the opposite sides, in the direction of the boundary-line; and those trees which are in the line shall be marked in addition with a smaller horseshoe mark above the other. [See Appendix T, diagram No. 7.]

Trees on or near boundaries.

115. Alignment stakes shall be inserted on the boundary at intervals of not more than 10 chains, with lockspits, the object being to provide marks visible one from another; and on boundaries exceeding 120 chains in length there shall be intermediate reference stations at intervals not exceeding 80 chains, which shall be marked for identification in alphabetical sequence.

[See Appendix T, diagram No. 8.]

Alignment stakes.

Reference Stations.

116. When a tree stands on a corner it shall be marked as provided in Regulation 101. [See Appendix T, diagram No.9.]

Tree on corner.

117. Rocks which may be upon a boundary-line shall be marked in suitable places with a pick-line whenever the character of the rock will admit of it; and if a corner of a portion be on a rock, it shall be marked with the parish number, and in the manner specified in paragraph 111. [See Appendix T, diagram No. 10.]

Rock on boundary or at corner.

118. When Crown land is to be measured adjoining a previously-defined portion, the marking or the common boundary shall be renewed; where a fence has been erected on the boundary, further alignment stakes and lockspits are not needed.

Re-marking of boundaries.

The obliteration of marking of a cancelled survey shall be limited to defacement of the corners, the boundaries to be shewn on plan by dotted black lines.

Obliteration of marking.

RESERVE, FEATURE, TERRITORIAL SURVEYS, AND ROADS.

119. For a reserve the reference-marks shall bear inscribed the usual letters significant or the purpose or the reservation, e.g., W.R., T.S.R., &c., unless directed to be numbered as a portion. [See Appendix T, diagram No. 11.]

Reserve.

120. At all reference points on feature surveys, special marks, as prescribed by paragraph 126 shall be inserted. At convenient places for the purpose of subsequent comparison of meridian the District Surveyor may require a bearing and distance to be recorded to a mark on any convenient tree or post distant (say) about 5 chains. The mark shall be a copper tack at the apex of a broad-arrow. [See Appendix T, diagram No. 12.]

Feature survey.

121. For county boundaries, the reference-marks shall bear inscribed the initial letters of the names of the counties adjoining, over a number in due sequence, as directed. For connection surveys reference-marks shall bear inscribed letters in alphabetical sequence over the last two figures or the year. [*Vide Appendix* T, *diagrams* 13 and 14.] The marks shall be distant from each other about one mile.

Country boundaries and connections.

122. A road shall be defined on both sides by trees marked in the prescribed manner; and split hardwood stakes, 3 inches square and 21 inches long, 18 inches in the ground, shall be inserted at all angles, and at intervals not exceeding 10 chains, and also at each mile of continuous measurement; there shall be lockspits at stakes on the side measured.

Roads.

123. Unless directed to the contrary, at each mile the nearest tree shall be marked, or in the absence of a tree within a reasonable distance, a reference post shall be used instead of a stake, bearing inscribed letters in alphabetical sequence over the two last figures or current year. [See Appendix T, diagram No. 15.] The particulars of bearing and distance from the marked tree to the mile-stake shall be observed and noted for reference as prescribed. [See paragraph 99.]

Miles to be marked on tree or post.

124. When a fence is coincident with one side of a road, the corner-posts shall be marked with a broad-arrow over the letters R.D. [See Appendix T, diagram No. 15.]

Corner-post of fence.

125. A reserved road through a portion shall be defined in the manner specified (*paragraph* 122), and stakes with lockspits shall be inserted at the points of intersection with the boundaries.

Reserved road.

SPECIAL MARKS.

126. In addition to the marking hereinbefore prescribed, it is required that there shall be occasional special marks, which may be capable of identification when, in the course of time, the ordinary marks by stakes, lockspits, and trees, may have decayed or may have been destroyed in process of settlement.

Special marks.

127. The character of such special marking must, to some extent, depend. upon surrounding conditions, e.g., in a country where there may be rocks, it would be sufficient to insert metal plugs in suitable places; where there are no rocks a quart bottle filled with a mixture of sand and cement, or a piece of galvanised-iron tube would be suitable.

Description of.

128. The metal plug for insertion in rock shall be of round copper or Muntz metal rod, not less than ³/₄-inch diameter, and not less than 3 inches long; and there shall be a deeply-inscribed broad-arrow, 4 inches long, with its apex very, near to the plug; and the plug should be fixed in position by melted sulphur, the top being (say) ¹/₂ inch below the surface of the rock.

Copper plug.

129. To fix a plug in rock - A hole is to be drilled somewhat deeper than the length, and about double the diameter of the plug. Melt sulphur in an iron vessel (an iron ladle with a long handle is best), and when the surface of the sulphur appears brown, add a like quantity of clean, sharp, dry sand; stir, and pour round the plug. The mixture sets quickly.

To fix plug.

130. For bottle marks mix clean, sharp sand and Portland cement in the proportion of 3 to 1, with sufficient water to make a good mortar; fill the bottle with same, and place it vertically, top upwards, 1 foot below the surface of the ground.

Bottle mark.

131. The galvanised-iron tube shall be of the sort ordinarily used for water supply, the rim to be not less than $\frac{1}{8}$ inch thick, the piece to be 1 foot long, and to be inserted vertically, with the top 1 foot below the surface of the ground.

Tube marks.

132. In road survey it is desirable that these marks be inserted in the alignment at suitable points about half a mile apart; they shall be on the same side of the road, and distant 5 links from a station or an alignment-stake, and in the same direction therefrom relatively to a terminal of the survey.

Position of marks for road survey.

133. In subdivision of Crown land, the selection of positions for special marks must he left largely to the discretion of the Surveyor, who in the process of measurement will become acquainted with conditions of the ground. It may be pointed out that it would be an advantage to have intervisible points suitably placed for reference on one boundary, so as to facilitate comparison of azimuth.

For country portion.

134. In feature survey, the special mark shall be placed at a station where there is a reference-tree. In the marking of any survey, rock marks are to be preferred.

For feature survey.

135. On the plan, the station or corner nearest to which the special mark is inserted, shall be indicated by two concentric circles, and amongst the notes on plan there shall be particulars.

Mode of indicating special mark on plan.

136. Marks for the survey mentioned in paragraphs 132 and 133 will be inserted only under specific directions from the District Surveyor.

To be inserted under special directions.

REPORTING WILFUL DESTRUCTION OF A GOVERNMENT SURVEY MARK.

137. It is desirable to report any case of willful destruction of a survey mark, when it may come under notice, and when the circumstances admit of prosecution of the offence under the Survey Marks Act, No. 56, 1902. [See Appendix F.] . The particulars required to enable successful prosecution are the full names and place of residence of the person offending; the place; the date of offence; the names of any witness and residence; the specific mark destroyed; the name of the surveyor by whom the mark was made for the purpose of Government survey - for there must be identification of the survey mark; and the names and designation of any official in the locality to whom it might be convenient to entrust the prosecution, e.g., Senior Police Officer or Crown Lands Bailiff, &c.

Survey marks – Protection of.

138. It is very desirable that any well-authenticated case be made the subject of immediate report to the District Surveyor, with a view to prosecution; steps being thus taken for protection of survey marks, the mischievous destruction of which causes much inconvenience and loss of time.

DRAWING. GENERAL DIRECTIONS.

139. The best mounted hand-made drawing paper shall be used for all plans.

Paper – Quality of.

140. Plans shall be drawn on paper of the following sizes, viz., foolscap page, single, double, or quadruple foolscap sheet; and the paper shall not exceed the size requisite for the survey, allowing ample vacant space for notations as to sales, issue of deeds, reservations, &c. It may be mentioned that much inconvenience is caused through insufficient space for notations. The size of roll plans shall be restricted to limits prescribed by the postal regulations.

Sizes of plans.

141. Plans of town and suburban lands, and of country lands measured under certain conditions, may be required to be drawn for photo-lithography.

Photo-lithography – drawing for.

142. A plan ordinarily shall not represent more than one portion; but for special reasons and with authority obtained the number may be increased.

Portions on plan.

143. Plans shall not be folded for transmission through the post, but shall be rolled on rollers, or otherwise protected from damage. Should a plan be damaged through want of proper care in transmission, the Surveyor will be required to furnish a duplicate at his own cost.

Transmission of plans.

144. A plan shall be accurately plotted, and if, upon inspection, found to be incomplete, faulty, or not up to the standard of professional work, it may be rejected.

Plan to be correctly and carefully drawn.

145. The bearings of all boundaries, traverses, &c., shall be stated relatively to the local magnetic meridian, or to that of adjacent survey when the azimuth of a previous survey is adopted.

Bearings to magnetic meridian.

146. Unless there is sufficient reason to the contrary, plans shall be plotted and shall read with the north point upwards.

Position of plot.

147. The magnetic north shall be shewn on every plan, and where the true meridian has been determined, the magnetic variation shall be stated. The particulars of observation shall be recorded in tabular form.

North point.

148. On a plan of an extensive survey the scale should be drawn during plotting, and should not be less than 12 inches in length; the scale of the plan should also in every instance be stated in writing, except when drawn for photo-lithography.

Scale to be drawn.

149. Plans of town allotments are usually to be plotted, to the scale of 4 chains to 1 inch; but in cases where the allotments may be so small as to render representation on that scale indistinct a larger scale may be used by direction of the District Surveyor. Where the allotments are to be sold by the foot frontage, the plan shall be drawn to a scale of feet, and the lengths stated accordingly. In the subdivision of a town or suburban allotment a plan of each part is to be furnished.

Scale – for town allotments.

150. Plans of suburban portions are usually to be plotted to the scale of 8 chains to 1 inch; but the scale may be varied by direction of the District Surveyor.

Scale – for suburban portions.

151. Plans of country portions of 1,920 acres or less shall be drawn to the scale of 20 chains to 1 inch; for patrons above that area, to the scale of 40 chains to 1 inch. When the form of an area less than 1,920 acres is such that the plan will be of inconvenient size, the smaller scale may be used.

Scale – for country portions.

152. The plan of any lease shall be drawn to the scale prescribed for the class of land to which it belongs, e.g., town, suburban, or country, but the scale may be increased where requisite.

Plan of lease – scale of.

153. Plans of surveys for the purpose of the Real Property Act shall be drawn on the authorised form (*Appendix* Z). A tracing, being an exact copy of the plan, shall be furnished on the authorised form. The certificate of survey shall be signed on plan and tracing. A certificate as to encroachment, &c., shall also be furnished on the approved form. (*Appendix* Q.)

Plans – Real Property Act surveys.

154. The scale to be used for feature and territorial surveys shall be 20 chains to 1 inch, unless otherwise directed.

Scale – for feature surveys.

155. Boundaries of portions and allotments shall be shewn by firm black lines; and the bearings and lengths of all boundary lines shall be distinctly written along them in black.

Boundaries of portions.

156. All bearings shall be recorded in degrees and minutes from north round by east to 360 degrees.

Bearings – how to be noted.

157. Traverse lines of surveys other than boundaries shall be numbered and drawn in blue colour (except for roads); and the bearings of lines and their lengths are to be written in black in tabular form on the plan.

Traverse lines.

158. The portion or portions represented by the plan shall be tinted; and, in addition, edging shall be used to define the computed area. The edging shall be applied with a brush.

Tinting and edging.

159. The following colours shall be used for illustrating plans unless otherwise directed:-

Colours to be used.

For plans prepared for photo-lithography, a tint and edging of blue.

For other plans of areas measured for alienation or lease, a tint and edging of carmine.

For public school sites, blue.

For reserves and areas to be dedicated, emerald green.

For cemetery sites and gold-field boundaries, yellow ochre or Indian yellow.

For reserved road or track, burnt sienna.

For stations and traverse lines, co-ordinate lines, meridians, direct bearings and distances, bearings to trigonometrical stations and distant points, numbers of traverse lines, and minor connections, blue.

For topographical surveys, see Appendix P¹

160. Bearings to distant or remarkable points or to opposite sides of rivers, &c., and direct bearings by calculation, shall be delineated in blue broken lines, and the particulars shall be written in like colours.

Bearings of the line not chained.

161. Red writing shall not be used on plans except for numbering the road and alignment traverse on road and alignment plans.

Red writing not to be used – Exception.

162. All direct bearings and lengths required for describing the relative positions of measured portions shall be calculated and written on the plan.

Connections.

163. Lines of coasts, rivers, creeks, &c., shall be shewn, where the position is determined with precision, by black lines, and, where otherwise, by broken black lines. Both sides of a watercourse shall be shewn, and an arrow is to be drawn indicating the direction of the current. Trigonometrical stations shall be shewn when they are upon or adjacent to portions represented on a plan.

Physical features, rivers, and creeks.

164. Hills and undulations within scope of the survey shall be carefully represented.

Trigonometrical stations.

Hills

165. The limits of swamps, forests, plains, lands liable to inundations, &c., shall be carefully represented on the plan. The position and extent of improvements, such as buildings, fences, clearing, ringbarking, &c., on lands measured, shall also be shewn, and particulars stated in a note on the plan. Where a fence is near a boundary, its relative position thereto shall be noted on the plan.

Other features, improvements, &c.

166. Roads reserved through portions shall be represented on the plan by black lines, the traversed side being indicated by a firm line, and the opposite side by a broken line. The cosecant distance, and bearing shall be stated when the road is 3 chains wide and over. The width shall be written along the course of the road, thus:- *Reserved road* 1 *chain wide*. Tracks shall be represented by brown bands.

Reserved roads

167. When a reserved road intersects a boundary, the distance from the point of intersection to a corner, also secant distance, shall be stated.

Connections to roads.

168. All boundaries shall be represented as they are found - e.g., as marked lines, walls, or fences, &c. - any discrepancies being clearly indicated, and explained so far as practicable in the letter transmitting plan.

Old boundaries.

169. Particulars of corners and reference marks shall also be indicated as found, e.g., stake found, tree found, &c. The names of grantees, conditional purchasers, or lessees of adjoining portions, with the areas and numbers of the portions or allotments, shall be written in black ink.

Old reference marks and particulars.

170. The geological formation of the land measured, its suitability for building, cultivation, agricultural or pastoral occupation, the supply of water, character of timber, herbage, &c., shall be recorded on the plan, either by writing across the portions, or, if found more convenient, in notes.

Topographical particulars.

171. On the plan of a portion, any area reserved or held under authorised occupation within the ambit of such portions shall be properly delineated.

Reserve or tenement.

172. All known names of rivers, creeks, hills, lakes, localities, &c., shall be written on the plan, care being taken to ascertain and adhere to the correct orthography.

Names of features and localities.

173. In extensive feature survey, the plan shall, for convenience in compilation, be plotted in sheets, and no sheet shall be more than 5 feet long. Meridian lines should be drawn through the stations at which meridian observations have been taken. The angle between the meridian of the traverse and the true meridian at each meridian station shall be stated.

Feature surveys – special directions for.

174. On plans of road and feature surveys co-ordinate lines shall be drawn in blue colour at convenient distances (preferably 10 inches apart), and the values of the lines shall be written in the same colour on the margin of the plan. Particulars of traverse, differences of latitude and departure, also co-ordinates, shall be stated in tabular form, the traverse written in black and the other information in pencil. The datum point of co-ordinates shall be such as to preclude minus values. Co-ordinates must be supplied only as regards the terminal points of the traverse, each mile tree or other salient point, and not for each traverse line.

Co-ordinate lines.

175. The parish number and area of a portion shall be so written and placed on the plan as to leave sufficient space to clearly set forth particulars of alienation.

Parish numbers to be placed conveniently.

176. Boundaries for territorial divisions, such as county, parish, municipal, and other districts, reserves, &c., shall be represented as shewn upon the table of distinguishing boundaries (*Appendix* U); and where necessary the particulars of the same shall be written in suitable position. Where several of such boundaries may be coincident, the most important one only shall be represented in the conventional manner, but the terms of such common boundaries shall be specified.

Distinguishing boundaries.

Omission of fractional quantities.

177. In the measurement of portions for alienation or dedication it is desirable to avoid as far as possible the introduction on the plan of fractions of an inch in town allotments, and fractions of a link in suburban and country portions; and also to avoid quoting seconds of arc in bearings - the object being to simplify the description for grant, i.e. to render it less voluminous. When a road is reserved out of a portion the area shall be specified as "exclusive of road." The following fractional quantities in excess shall be omitted according to the area specified:-

In portions of not more than 1 rood

More than 1 rood and not more than 2 acres

More than 2 acres and not more than 10 acres

Less than ½ perch.

Less than ½ perch.

Less than 1 perch.

More than 10 acres and not more then 40 acres

(if bounded by right lines) Less than 10 perches. *

More than 10 acres and not more then 40 acres

(If bounded partially by a watercourse.) Less than 1 rood.

More than 40 acres and not more then 320 acres

(if bounded by right lines) Less than 1 rood. *

More than 40 acres and not more then 320 acres

(If bounded partially by a watercourse.) Less than 2 roods.

More than 320 acres and not more than 640 acres Less than 2 roods.

More than 640 acres

Less than 1 acre.

In surveys under the Real Property Act for exchange and surrender the areas are to be quoted to the nearest perch.

178. The reference to corners of country and suburban portions shall be noted on the plan in the following tabular form, the corners being identified by letters in alphabetical order. Abbreviations, dots, dashes, or the word ditto are not to be used.

Reference to corners.

<u> </u>		, acts, ausiles, ci			
Reference to Corners.					
Corner.	Bearing.	From.	Distance in	Number on	
			links.	tree.	
A	360°	Bloodwood	50	15 – 16	
В	265°30'	Ironbark	17.5	17	
С		Post at corner		17	
D	71°45'	Swamp Oak	24	17	
Е		Rock at		16, 17	
		corner			

179. The title to the plan shall be written without abbreviations, to explain clearly what the plan is intended to represent, stating the numbers of allotments or portions measured, the town, parish, county, land district, and shire, if within any or all of these.

Title to plan.

^{*} Note. - The perches (if any) should be entered as 10, 20 or 30 perches, as the case may be, i.e., units are to be omitted.

180. The words "applied for by," with the name of the applicant in full, shall be written under the title, and not on the portion itself; and the section of the Act under which the land is applied for shall be stated and also the land agent's registration No. Ample space should be allowed between title and drawing for future notations.

Particulars under title.

181. Where a measurement is made for a purpose other than alienation, such as special lease, reserve, site for public school, cemetery, &c., the particulars shall be clearly set forth under the title.

Measurement other than for alienation.

182. Particulars of situation, e.g., within a pastoral holding (leasehold or resumed area), or within a gold or mineral field, together with the date and number of the letter reporting survey, shall be recorded amongst the notes on the plan.

Notes on plan.

183. The word "lot," which is specially applied to lots for auction sale, shall not in any case be used on the Surveyor's plan; "allotment" shall be applied to town or suburban allotments in sections, and "portion" to other suburban and country lands.

The term "lot" not to be used.

184. In connection with surveys under the Real Property Act or for the purposes of that Act, a certificate and description to comply with the provisions thereof shall be furnished. [Appendices Q, Z.]

Certificate by surveyor.

185. The date of survey in certificate on plan should be the date on which measurement was completed on the ground.

Date of survey.

186. All plans shall be transmitted as soon as possible after survey.

Transmission of.

187. Whenever an amended plan, or plan of an amended survey is transmitted, it should be under cover of a letter, specially stating particulars of original survey. The plan and letter must be headed "Amended Plan," or "Plan of Amended Survey," as the case may be.

Amended plan of survey.

188. Each plan shall be accompanied by a separate letter reporting full particulars, &c., and therewith shall be transmitted a tabular statement on the approved form, setting forth particulars of the traverse, reduced bearings, and the differences of latitude and departure; and, in the case of a measured portion, the particulars of computation of area shall also be inserted. [*Appendix* G.]

Tabular statement of computation.

ROADS.

189. The best mounted drawing paper shall be used for all plans of roads.

Paper, quality.

190. The survey shall be plotted on the paper longitudinally in the direction of the road, so as to be confined within convenient limits, with the north upwards.

Position of plot.

191. Where the road is under 5 miles in length, measured from end to end in a direct line, the plan shall be plotted to the scale of 10 chains to 1 inch; and when of greater length to the scale of 20 chains to 1 inch; and sometimes when there is little or no topographical detail, and the road is of considerable length, to the scale of 40 chains to 1 inch; but in the last case, and possibly occasionally in the former, diagrams of parts to a larger scale may be requisite, and should be drawn, in convenient position on the plan.

Scales.

Diagrams.

192. The road shall be delineated in red colour. The preliminary traverse (if any), measured lengths and bearings for connections, cosecants in roads of 3 chains wide and more, also bearings to trigonometrical stations, widths of roads, and such particulars of mile-posts as may be written along the traverse, shall be drawn and written in blue colour. The boundaries of all alienated land, with all particulars appertaining thereto, all buildings, fences, rivers, watercourses, and other topographical detail, and any roads to be closed or granted in lieu, shall be delineated in black, also any building within 150 links of the road, although the owner may have consented to the road. Doubtful boundaries shall be indicated by black broken lines.

Delineation

193. Tracks shall be indicated by brown lines. The road to be opened shall be coloured red, and any roads which are to be closed or granted in lieu of that to be opened shall be coloured blue; other roads defined by survey shall be coloured brown. Except for the purposes specified, the colours red, blue, and brown shall not be used on road plans.

Colouring.

194. All writing on road plans shall be black, except as prescribed in paragraphs 159, 160, 161, 174, and 192. Particulars of reference to mile-trees may be supplied in tabular form as for corners. [See paragraph 178.]

Writing.

195. The title or the plan shall express as clearly as possible the description of the road or the land to be resumed for notification in the Gazette. Attention is directed to Appendix R.

Title of plan.

196. A schedule on the approved form shall accompany the plan of a road (except where it is not necessary to resume alienated land), and shall contain complete particulars as to ownership and occupation of land affected, enclosures, &c. Also, wherever it is requisite to remove or re-erect fences, or provide for new fences, a separate return shall be supplied on the approved form. [Appendix L.]

Schedule.

197. The plan, schedule, and return of fencing shall be subscribed by the Surveyor, and shall bear the date and number of letter reporting survey.

Return of fencing.

198. Any enclosure severed by a road should, if possible, be delineated in its entirety, so that claims for fencing and severance may be dealt with, but when too extensive to be brought within scope of the survey and plan, particulars shall be afforded in the report. The traverse of fences merely for this purpose is not required.

Plan and returns to be signed.

199. The letter reporting survey shall contain particulars of the character and value of the land to be resumed, and that to be given in lieu, and particulars and value of improvements thereon, the enclosures severed, and their uses, the description of the fencing, and sites for water supply. [See Appendices L, M, N, and R.]

SPECIMEN PLANS.

Enclosure severed by a road.

Letter reporting survey.

200. Attention is directed to the specimen plans, which are illustrative of the foregoing instructions. [Appendices Y, Z, Za, Zb, R, S.]

RULES FOR CORRESPONDENCE.

201. All letters shall be clearly written or typed upon whole sheets or serviceable hand-made foolscap paper, with a third margin, with black ink, and initialed with the subject-matter of surveyor report, e.g., "Conditional Purchase," "Roads," "Improvement Lease," &c., &c., The writing shall follow on consecutive pages. [Appendices Wa, b, c, d, e.]

Letter - form of.

202. The particulars should be written briefly at the head or each letter, not encroaching on the margin, a clear space of an inch being left above such heading.

Heading.

203. The Surveyor when transmitting a plan shall report full particulars as to survey, e.g., date, situation, proclaimed division, district, reserve, shire, or mining area.

Particulars of survey.

204. Each letter must be restricted to one subject; and all letters or reports shall be dated and numbered consecutively, as of the year, and addressed to the District Surveyor. Replies to query papers on points of survey and subordinate memoranda should not be numbered as letters. The corners of a paper shall not be turned up for the purpose of writing an explanation or reply; but writing shall be continued in proper sequence.

Subject and number of letter.

205. The number and date of any instruction, letter, or B.C. memorandum replied to, with the number of official registration, should invariably be quoted.

Registration No. of instructions to be quoted.

206. There shall be no abbreviations used in letters or reports except for quoting the recognised abbreviations for registration. [*Appendix* J.]

Abbreviations.

207. All official letters and packets shall be forwarded under envelope marked "O.H.M.S." bearing the Surveyor's name, designation, and date of despatch on the outside left-hand lower corner.

Envelope to be endorsed.

208. All original papers forwarded with instructions must be returned under cover of the letter or report dealing with the same.

Papers to be returned.

209. In returning a letter or B.C. memorandum conveying instructions after action has been taken on the same, particulars shall be briefly endorsed by the Surveyor, e.g., "Replied to by my letter, No. 99-5"; "Dealt with by survey under letter 99-6"; "Noted and returned." Papers forwarded under B.C. as an instruction should not be returned until action has been completed.

Action taken to be endorsed on papers returned.

210. When returning papers referred for information, or upon which action may have been taken, the B.C. reply shall be written next following the instructions or inquiry. [See paragraph 204.]

B. C.'s to be written consecutively.

211. A register shall be kept by the Surveyor, setting forth particulars of all instructions received and action taken thereon. Such register will be supplied on application to the District Surveyor, is the property of the Department, shall be kept up to date, and shall be forwarded to the District Surveyor whenever demanded.

Register of instructions to be kept.

REPORTS.

ON CROWN LANDS AND SETTLEMENT.

212. In a letter reporting on the measurement and occupation of Crown land, unless otherwise directed, full particulars are required as to character of soil, suitability for residential purposes, and value of land, as to access, as to water supply, as to forest, the description of trees, condition of same, and especially whether the trees afford timber suitable for the purposes of construction, or are of commercial value, as to improvements, &c.; proximity to a town, or port, or railway, or main thoroughfare, or school or butter factory, or being on or adjacent to a navigable river or tidalwater which may constitute elements of value. In describing open country, it shall be stated whether naturally clear of timber, or whether trees have been felled and burned, or grubbed, or burnt out after being killed.

General information.

213. The date of erection, value, and reputed ownership of improvements should be ascertained where practicable; full details should be supplied, such as the length, character, and value of each line and class of fencing, where there are various and different classes of fence, or different owners are affected; in the case of netting fences the value of fence without netting and the value as netted should be given separately; the value of a fence for removal purposes when not in a suitable position should also be furnished; the cubic content (in yards) and value of a tank or a dam; the description, depth, and value of wells and appliances; the number of rooms and material used for, and value of any house; extent and value of clearing, ringbarking, &c. The report shall be complete in itself, without recourse being necessary to a plan for any such particulars.

Improvements.

214. In a letter reporting feature survey particulars of the physical character of the country shall be afforded.

Feature survey.

215. The Surveyor shall furnish reports on the printed forms approved by the Department when so directed by the District Surveyor.

Printed forms.

216. When portions are measured in a proclaimed gold or mineral field, a distinct statement to that effect is required. Where any person is in authorised occupation under the Mining Act, the number and date of miner's right, or business license, or mineral lease, or other authentic particulars, shall be furnished. Where priority of occupation is of importance with respect to title, careful inquiry and verification of dates will be needed.

Survey in proclaimed gold or mineral field.

217. Particulars shall be furnished wherever fencing exemptions can be recommended in respect of conditional purchase or other holdings.

As to fencing exemptions.

RESERVES.

218. The report shall be comprehensive in its character, setting forth public requirements for the reservation, and specifying the purpose; and all such other information as may be requisite to support the recommendation for, or to warrant the revocation of a reserve, and a diagram shall be furnished from which a description of the land may be prepared.

Report on reserve.

ROADS UNDER THE PUBLIC ROADS ACT.

219. When a Surveyor is required to report on an application for a road, he shall carefully inspect the country along the proposed route, and report fully on the points hereunder mentioned, furnishing a sketch in illustration of his report. The first consideration should be public requirements and conditions favourable for traffic; the second, the least possible interference with, or injury to, private property:-

Report on application for road.

Public requirements.

Probable traffic.

Course of the proposed road, width thereof, and alternative routes (if any). Ownership and occupation of land affected.

Character and value of land to be resumed, and land to be given in lieu (if any).

Damage by severance, or gain by betterment (if any); and resumption of severed land.

Interference with watering arrangements and sites for water supply.

Enclosures severed, and their uses.

Necessity of removing or of erecting new fencing, and cost thereof, and whether public gates may suffice.

Granting of unnecessary roads or Crown lands by way of compensation.

Probable claims for compensation.

Right of user (if any).

PUBLIC GATES.

220. In dealing with an application for a ,public gate, the Surveyor shall report full information concerning the points hereunder mentioned; also supply a sketch showing the position of proposed gate, and shall submit his opinion whether permission for such gate should or should not be granted:-

Particulars of road, e.g., description, whether dedicated under the Public

Roads Act, or otherwise a thoroughfare.

Particulars of present traffic.

Probable future traffic.

Whether a mail route, and traversed by a mail conveyance.

Whether the road is under trustees, a Shire or Municipal Council, or in charge of an officer of the Public Works Department.

Whether there is any other route which would now or at any future time render unnecessary the road under reference.

Whether applicant is the owner or occupant of land on both sides of the site of the gate applied for; and, if not, the names of the other owners and occupants.

The character of soil and grade at site of proposed gate, and whether formation of approach is necessary.

The damage (if any) to proprietary interests by the fencing of road, or the refusal of public gates.

The description and value of fencing, forming the enclosure.

Any other public gates and their relative positions to each other.

The width of opening which would be most desirable.

MODE OF REMUNERATION FOR SURVEY.

Public gates report.

221. A Surveyor shall be remunerated for services which he may be authorised to perform according to the Schedule of, Prices hereinafter set out, and payment will be made after the service shall have been approved by the Surveyor-General, District Surveyor, or officer duly authorised in that behalf, but an advance not exceeding 75 per cent. of the amount due may be paid ,before such approval on certificate of the Surveyor General, District Surveyor, or other duly authorised officer.

SCHEDULE OF PRICES.

- 222. For right line boundaries measured and marked, ninepence (9d.) per chain up to 80 chains, and sixpence (6d.) per chain for the remainder, for each portion.
- 223. For marked new corners of portions and corners of town sections and cemeteries five shillings (5s.) each; for each other corner two shillings and sixpence (2s. 6d.).

For remarking old corners, &c.:-

- (a) If both the old tree and peg are gone 5s. for marking a new tree with the broad arrow and old numbers and replacing peg
- (b) If the old tree and the broad arrow and old numbers thereon are in existence but peg gone, 2s. 6d. for the new peg.
- (c) If the peg is in existence, but the old tree is gone, or if the old number or numbers are not visible after removing the superincumbent growth (if any), 2s. 6d. for marking a new tree with the broad arrow and old numbers.

Circumstances to be fully reported in letter transmitting plan.

- 224. For obliteration of corner marking of cancelled portions, ls. per corner.
- 225. The fees prescribed for survey of town allotments and sections shall be subject to a decrease of ten (10) per centum unless the Surveyor-General or District Surveyor otherwise directs.
- 226. For survey of features, ranges, watercourses, tracks, and coast-line, sixpence (6d.) per chain.
- 227. For connections where there may be no natural features to trace, or along previously marked lines, fourpence halfpenny (4½d.) per chain.
- 228. For roads, railways, and other lands not exceeding 3 chains in width reserved out of portions and marked on both sides, ninepence (9d.) per chain including cosecants.
- 229. For roads, driftways, railways, and other lands exceeding 3 chains in width, reserved out of portions and marked on both sides, sixpence (6d.) per chain on each side.
- 230. For survey of roads under the Public Roads Act, one shilling (ls.) per chain of road, including cosecants.
- 231. For subdivision of a portion. The subdividing line shall be paid for at boundary rates (paragraph 222). Connections and remeasurement as directed by paragraph 62, sixpence (6d.) per chain.
- 232. In respect of adjoining areas the survey to be paid for shall not include lines previously measured by the same Surveyor within two years; but in respect of leases other than conditional leases, conditional purchase leases, and residential leases the survey to be paid for shall not include lines previously measured unless the District Surveyor has directed remeasurement.

- 233. For a comparison of azimuths, ten shillings (10s.).
- 234. For determination of the magnetic variation, £1.
- 235. For a special mark, two shillings and sixpence (2s. 6d.).
- 236. An allowance at the rate of one shilling per mile shall be payable to the Surveyor when travelling with camp equipment and party, for the purpose of effecting surveys under these Regulations; such allowance will be payable from a place to be named by the District Surveyor, and from survey to survey. A Surveyor shall so arrange his work as to obviate unnecessary travelling. In all cases where travelling is charged for, full particulars of the route travelled must be stated.
- 237. The application of the Schedule of Prices is exemplified by diagrams. [*Appendices*, Ia, Ib, Ic.]
- 238. For a tracing furnished in terms of paragraph 153 a sum of 10s. 6d. will be allowed.
- 239. In connection with measurement of country lands, when a report upon form L.L.B. 78 or any approved printed, form of similar character shall be specifically directed, there shall be fees payable at the undermentioned rates, except in cases of subdivision, when amended reports may be required at half rates. [Appendix H.]

	t	S.	a.
For an area not exceeding 640 acres	0	10	0
For an area over 640 acres and not exceeding 2,560 acres	1	0	0
For an area over 2,560 acres and not exceeding 10,240 acres	1	10	0

240. In order to provide adequate remuneration for services to be performed under special or very difficult conditions, an increase to the rates in the Schedule of Prices for services specified in paragraphs 222, 223, 226 to 231 may, on approval of the Minister, be held to apply within specific limits, and such increase may, on like approval, at any time be varied or cancelled. For the items specified in paragraphs 224, 233 to 236 there shall be no increase or decrease on Schedule of Prices.

Special remuneration.

241. It shall be competent for the Surveyor-General to let by special contract, by or on behalf of the Minister, for a specified sum, or at an increase or decrease upon the Schedule of Prices, surveys such as the division of an area of country into portions, laying out roads, and topographical and other surveys. Payments for inspections and reports may be arranged for at special rates.

Special contract.

242. For services to which the Schedule of Prices may not be applicable, remuneration may be allowed at a rate not exceeding £3 3s. per diem for field service and not exceeding £2 2s. per diem for office service.

Remuneration by daily rate.

ACCOUNTS.

243. Attention must be bestowed on the preparation of accounts, which will; not be accepted if vitiated by erasure or interlineation. Printed forms will be supplied on requisition.

Preparation of accounts.
Printed forms.

244. For portion surveys each length charged is to be recorded on fourth page of voucher Form "A." Where a line is divided, part being charged for at one rate and part at another, each part shall be distinguished by a small mark, such as *.

Portion measurement.

245. Accounts for inspections and reports made at time of survey of a portion shall be included in account for such survey, and placed conveniently below local increase item on Account Form "A"; when not made at time of survey, Account Form, "B" to be used. (*Appendix Id.*)

Reports.

246. Accounts for tracings in terms of paragraph 153 shall be included in account for such survey, and placed conveniently below local increase item on Account Form "A."

Tracings – Real Property Act Surveys.

247. All moneys due will be paid into one of the banks in the city of Sydney to the credit of the Surveyor, or of any other person duly, authorised by him. A Surveyor will be advised of each payment to his credit at a bank when it is made.

Surveyors to have bank account.

248. An authority in general terms in the approved form for payments into a bank shall be duly signed by the Surveyor and furnished whenever required.

Authority for payment to credit required.

249. Upon receipt of an account for service duly certified by the District Surveyor, an advance may be paid not exceeding 75 per cent. on the amount specified as due by that officer.

Advance on account.

250. An account shall be rendered for each survey performed, and shall be initialed according to its class of survey, e.g., Roads, Feature Survey, Conditional Purchase, Homestead Selection, Homestead Farm, Crown Lease, &c.

Separate account for each class of survey.

251. An account for service to be paid for under the daily rates shall be rendered as may be directed for each special service, and on the printed form provided for that purpose. Such account shall specify full particulars of the service performed, e.g., the time occupied in the service, both field and office severally, the linear measurement or area, &c., and shall be transmitted with the letter reporting service.

Account for service at daily rate.

252. The charge for service at daily rates will be subject to consideration, and if in the opinion of the Surveyor-General, upon report of the District Surveyor, the charge is deemed to be excessive for the service performed, it may be reduced.

Amount may be reduced.

253. Accounts should be rendered if possible during the financial year in which the service has been performed, or not later than twenty-one days after the close of that period; otherwise delay may occur in payment.

Accounts to be rendered during financial year.

254. A Surveyor will be duly advised by the District Surveyor of particulars of alteration made in an account at time of passing the same for settlement; and if he shall disagree with any alteration he may forthwith submit a written protest setting forth his grounds of objection; but no protest shall be entertained unless submitted within one month of his being advised as aforesaid.

Surveyor to be advised of alteration of an account.

255. No claim in respect of any correction, reduction, or omission from an account shall be entertained after a lapse of one month from the date of advice of passing the same for settlement.

Claims cannot be entertained after one month.

256. The appendices herein mentioned shall be held to be part of these Regulations, and to exemplify their application.

Appendices.

CONTINGENCY.

257. Reference should be made to the District Surveyor as to the course to be pursued in any case not provided for in these Regulations.

Contingency.

Submitted,-FRED. POATE, Surveyor-General. 2/12/1914.

Approved, J. L. TREFLE,
Minister for Lands.
3/12/1914

Mins., 1914, 9051.

I acknowledge that I have this day received a copy of the foregoing Regulations, and I agree with the Surveyor-General on behalf the Government of New South Wales, and declare that all work at any time hereafter done by me for the said Government, under instructions from the said Surveyor-General, a District Surveyor, or an officer specially authorised on that behalf by the Surveyor-General, shall and will be done and performed under and in accordance in all things with the said Regulations and of the instructions forwarded to me; that payment for such work is to be made to me at the rates, and at the times, and in manner mentioned in the aforesaid Regulations, whether the aforesaid Regulations are or are not referred to in the instructions from time to time forwarded to me; that in respect of all work done by me I shall not have any claim or demand in respect of any matter or thing not provided for in the aforesaid Regulations; and that the acceptance by the Surveyor-General, District Surveyor, or officer duly authorised for that purpose, of any work done by me as before mentioned shall be a condition precedent to my having any claim or right of action for any money alleged to be due to me for work done under the aforesaid Regulations.

Dated at the day of A.D.

Witness to Signature -

APPENDICES.

APPENDIX A.

INSTRUMENTS to be Provided by a Surveyor, and to be Subject to Approval.

One (1) Theodolite, not less than 5 inch plates.

A steel or invar band 66 feet long; a steel or invar band not less than 66 feet long to be kept for adjusting and testing the chain used for measurements.

One set of light steel bands, not less than 500 links long

All necessary surveying instruments.

All necessary drawing instruments.

APPENDIX B.

LATITUDE OBSERVATIONS.

Station	Date.	Star.	Obs.	Merid	lian	Lat	itude		Mean.			
			Al	titude	;							
			0	6	"	0	6	"	0	6	"	
D	22 nd September, 1887 {	α Aquilae	50	12	33	31	13	41	} 31	13	25	
	22 September, 1887 (α Cygni	13	57	33	31	13	09	3 31	13	23	

OBSERVATION FOR MERIDIAN.

Station.	Date.	Latitude.	Star.	Survey bearing at elongation	True bearing at elongation.	Variation.	Mean.
		o , ,,		0 ' "	0 ' "	o ' ''	0 ' "
			δ Muscae	194 21 40	202 27 26	8 5 46	
A	18 th Aug, 1887	31 1620S	β Centauri	207 55 0	216 0 46	8 5 46	8 6 9
			β Gruis	119 37 0	127 43 54	8 6 54	
			δ Muscae	194 24 5	202 27 13	8 3 8	
В	25 th AUG, 1887	31 1520S	α Gruis	119 43 30	127 47 31	8 4 1	8 3 26
ь		31 13203	β Centauri	207 57 55	216 0 21	8 2 26	8 3 20
			β Gruis	119 40 35	127 44 42	8 4 7	
С	11 th Nov, 1887	31 1310S	α Reticuli	139 37 00	147 38 6	8 1 6	8 1 6
			γ Trianguli Aust	197 42 20	205 39 41	7 57 21	
D	22 nd Sept, 1887	31 1325S	α Eridani	133 29 00	141 27 45	7 58 45	7 58 11
			α Trianguli Aust	197 1 00	204 59 26	7 58 26	

OBSERVATION FOR MERIDIAN.

Station.	Date.	Latitude.	Star.	Obs	s. Al	t.	1	arin by rvey			rue irinș	ς.	Var	iatio	n.	M	ean												
		0 ' "		0	6	"	0	6	"	0	6	"	0	6	"	0	6	"											
				40	47	10	139	16	30	147	33	36	8	17	6														
1014	4 th Jan, 1889	21 40.040	α Crucis	α Crucis	α Crucis	41	2	15	139	19	10	147	36	36 49 8 17 39	0	17	1.4												
10M		31 4004S				α Crucis	α Crucis	α Crucis	α Crucis	α Crucis	α Crucis	α Crucis	α Crucis	α Crucis	41	21	30	139	23	50	147	41	13	8	17	23	8	17	14
							42	36	40	139	44	50	148	1	40	8	16	50											

APPENDIX B.

DETERMINATION OF MEAN HIGH WATER.

There are so many influences tending to disturb the rhythmical flow of the tides that observations extending over at least 12 months are necessary to obtain accurate results, but the determination of Mean High Water Level, which by Common Law, is the boundary of all land having frontage to navigable waters, is arrived at with sufficient accuracy by a much simpler process. A mean of all the high tide readings on a gauge during one lunation will give approximately the level required, care being taken to obtain the height of the night tides as well as the day tides. This is rendered necessary from the fact that in summer the day tides and in winter the night tides are the higher, the inequality becoming greater as the moon's declination, either north or south, increases. In spring and autumn there is very little difference. The factors which tend to increase the height of the tide being:-

- (a) the moon with southern declination,
- (b) the moon in perigee,
- (c) long continued southerly winds,
- (d) a very low barometer.

Care must be taken to avoid as far as possible any combination of the above or the opposite conditions.

When Mean High Water is to be fixed on a long flat with gentle slope, more extended observations will be necessary, as a couple of inches in vertical height in such case may mean a difference of many acres of land on a long frontage.

Observations to obtain the value of Mean High Water should never, of course, be taken when fresh water in large quantities is coming down the rivers or creeks flowing into the estuary.


In all estuaries where automatic tide gauges are established, the level of Mean High Water as recorded thereon is to ,be adopted and the level at which Mean High Water is defined is to be referred to the zero of such gauge and recorded on the plan.

RULE FOR APPROXIMATE DETERMINATION OF MEAN HIGH WATER IN AN ESTUARY WHEN AN AUTOMATIC TIDE GAUGE HAS BEEN ESTABLISHED.

On the same day - As the difference in level between high and low water registered on the automatic tide gauge is to the difference between the same tides at place of observation; so is the difference between high water on the automatic tide gauge and the height of mean tide recorded thereon, to the local difference between observed and mean high water. The quantity thus found should be subtracted from the local reading of high water; if the reading of high water of that tide on the automatic tide gauge is greater than the height of mean tide recorded thereon, or if less it should be added.

After Mean High Water has been determined, a ready method of defining it on the foreshore is to wait until the level of the water coincides with that height and then insert stakes along the contour of the water line.

METHOD OF OBSERVING THE RISE AND FALL OF THE TIDE



A float chamber of galvanized iron or timber about six inches internal diameter (*see* Sketches in margin), should be erected in at least 18 inches of water at low tide, to which a tide board should be attached as indicated in sketch. A hole not more than half an inch in diameter should be made at the bottom of the float chamber. This will ensure free access of the water while eliminating all wave action. A float, which may conveniently be made of a meat or jam tin, weighted with sand for stability with a light indicator attached to it should be placed in the chamber. As the tide rises and falls this indicates on the tide board the level above zero. A drop of grease in the float chamber will enable the surveyor to ascertain the water level on the float with accuracy

APPENDIX D.

ALIGNMENT OF STREETS.

1. The setting out and defining of carriage ways and of footways in streets and public places, commonly known as alignment, is carried out by Lands Department on behalf of Municipal and Shire Councils, under Sections 27 and 28, "Public Roads Act, 1902," and in accordance with the provisions of Section 95 (I) (d) Local Government Act, No. 56.1906.

Power to align streets.

2. The carriageway in a street 66 feet wide shall, as a rule, be 42 feet and the footways 12 feet on each side. These may, however, be increased or decreased according to the breadth of a street, and the requirements of a Council. If the street be not parallel, the carriageway only should be left of even width, unless circumstances warrant both the carriageway and footways being so treated.

Width of carriageways and footways.

3. Full information respecting holdings abutting on the streets should be obtained plans of original surveys and subdivisions should be inspected, and perusals made of the descriptions of grants and deeds of conveyance of adjoining lands, in order to ascertain the original intention with respect to the location of the streets. If it is found that the position of any street as defined on the ground is not in accord with such documentary evidence, such street should be located as nearly as possible in the position originally assigned to it, having due regard to the occupations adjoining it, and also to avoid unnecessary interference with vested interests. The original width should always be adhered to, unless the existence of permanent structures would fully warrant a slight diminution. The Council should satisfy the Surveyors that private subdivision streets have been dedicated to the Public.

Plans and descriptions of grants and subdivisions to be perused.

4. Connections should be made to a Trig. Station when practicable, and to the nearest adjacent alignment survey for comparison for azimuth.

Connection to Trig. Station.

Two or three permanent marks should also be sunk into the ground in suitable places, and connection thereto shewn upon the plan.

5. Both kerb lines are to be measured and radiations taken from alignment posts to permanent buildings, both to be shewn upon the plan (see Specimen Plan and Diagram D, *Appendix* S).

Kerb lines.

6. Encroachment by structures of a permanent character and fences upon the footways should be located by measurements from the kern lines, such measurements to be shewn upon the plan in black ink. All buildings within four feet of the building lines should, if possible, be located and shewn upon the plan.

Encroachments.

7. Connections should be made between alignment posts at the intersections of the street as shewn upon Diagrams A, B and D, *Appendix* S.

Connection at intersection of streets.

8. The markings of the alignment should be placed at the intersection of the kerb and building lines as shewn upon Diagrams A and B, *Appendix* S, unless prevented by obstructions, in which latter case, such marking may be placed along the kerb line, and the distance from the intersection noted upon the plan (see also Diagram A). An angle in a kerb line should be marked as shewn upon Diagram C, *Appendix* S, and if the intersections of streets are not intervisible, markings may be introduced at suitable intervals, not more than ten chains apart.

Marking of alignment surveys.

9. Alignment markings should not be placed at the intersection of aligned streets with those not yet aligned (see Specimen Plan, *Appendix* S).

Where marking unnecessary.

10. Streets necessitating alignment by surveys should be measured and marked in accordance with Diagram E, *Appendix* S. Full information with respect to measurement, together with calculation of curves, to be indicated upon the plan as shewn in Diagram E.

Measurement and marking in curved streets.

11. Wooden posts wrought stones, cement blocks, or iron castings may be used for marking the alignment, which should be supplied by the Council; and be in readiness at time of survey.

Material used in marking.

12. The Surveyor should see that the necessary markings have been placed in their proper positions before transmitting his plan of survey, which fact should be reported in his letter of transmission.

Surveyor responsible for marking.

13. The plan of survey should be plotted to a scale of either one or two chains to an inch, according to the amount of information required to be shewn; plan to be neatly drawn upon the best mounted drawing paper, the writing to be in coloured inks as shewn upon Diagrams A to E, and tinted in accordance with "Specimen Plan." (*Appendix* S).

Drawing of plan, colours to be used.

14. The various classes of buildings should be shewn upon the plan and indicated by distinctive colours, also a schedule of the streets proposed to be aligned with particulars as to terminals, width of carriageways and of footways, as well as the extent of encroachments, &c. Alignment markings to be indicated by black squares (see Specimen Plan, *Appendix* S).

Tinting of building. Schedule of streets.

15. The boundaries of grants, if correctly located, to be shewn upon the plan in firm black lines, and by broken black lines when their location is doubtful; the names of grantees and areas also to be shewn. When building lines are identical with grant boundaries, it will be sufficient to note upon the plan the original lengths of such boundaries in black ink, for purpose of comparison. Information respecting private subdivisions to be shewn in brown lines.

Boundaries of grants and private subdivisions.

16. The names of owners and occupiers of any buildings encroaching upon the streets, together with the extent of such encroachments, should be indicated upon the plan, and full particulars with respect thereto must be stated by the surveyor in his letter of transmission.

Owners of building encroaching.

17. The relative position of the kerb line to permanent structures (especially public buildings) to be determined by measurement and particulars thereof shewn upon the plan.

Permanent structures.

18. The field notes of survey to be transmitted with the plan.

Field Notes.

19. The various angular and lineal measurements regarded as necessary to complete alignment surveys will be found delineated on Specimen Plan and Diagrams A to E, *Appendix* S, to which special attention is directed.

Information regarded as necessary.

APPENDIX E.

GENERAL CEMETERY.

Par 95.

In selecting a site for a General Cemetery the following points should be observed, viz.: - The Cemetery must be outside the town limits; as a general rule, the distance should not exceed, two (2) miles from the probable nucleus of town settlement, and therefore may be within suburban limits. The position should be remote from the noise and interruption of traffic, but easy of access; the site should be elevated and not in close proximity to a watercourse; the soil should be friable, and should be tested by digging a pit at least 6 feet deep, such pit to be indicated on plan; and the conditions should be otherwise suitable for burial purposes.

Selection of site.

A Cemetery is dedicated under the Crown Lands Consolidation Act; and in respect of survey it is convenient to treat the area as a reserve for a public purpose; and it should be defined accordingly on the ground by marking the reference trees at Dedicated area.

TED**X** ---1 ----

Mode of marking.

corners, or the corner-posts, thus, CEMETERY, and numbering the allotments thus, 1, 2, 3, &c., as of town section.

The area to be reserved for a General Cemetery, as a rule, should not be less than 10 acres, but in order to economise expenditure in fencing and, preparing the ground, only a part of the area (not less than, say, 3 acres) should be subdivided for present use and dedication.

Area.

Design.

The design of subdivision should be adapted to the natural conditions of the site, and should be such as will admit of convenient extension of allotments when needed. The principle of design should be that there shall be one entrance to the Cemetery, and a main drive affording access to the larger burial grounds, from which it may sometimes be requisite to have a path to one or two of the smaller grounds. The areas of allotments should be proportionate to the numerical strength of the several denominations according to the census returns; but due regard should be bestowed to the local predominance of, or the absence of, any sect or sects. No allotment should be less than 20 perches, and where there is an ample and suitable area available, should not be less than 1 rood. When there are no members of one or more of the less important sects resident in the locality to be served, it is unnecessary to layout separate grounds for them - e.g., Independents, Quakers, Methodists, &c., or Jews; therefore, after providing for all probable local requirements, it is expedient to allow the residue of the Cemetery area to remain unallotted, i.e., available for future distribution.

An allotment should be set apart for unsectarian interment, the area of which will be dependent upon the design of subdivision, and should not be less than ¼ acre.

Unsectarian burial grounds.

It is desirable to leave an area for ornamental plantation around a Cemetery, and the arrangement thereof may admit of providing sites for a caretaker's residence, waiting-rooms, &c.

Ornamental plantation and caretaker's residence.

The plan should be drawn to a scale of 2 or 4 chains to 1 inch according to the amount of detail involved, and should be initialed -

Plan of a General Cemetery

at Parish of

County of

to be dedicated under the Crown Lands Consolidation Act.

The area of the Cemetery in its entirety should be tinted yellow, and the boundaries of allotments should be edged with a darker tint of the same colour. The areas of the several allotments should be stated in figures.

Colours to be used.

The letter reporting survey should be comprehensive; it should set forth the circumstances of allotment, especially as to local requirements; it should also contain information as to local prices for fencing materials and gates, with recommendation as to the most suitable description of fence and cost of erection, particulars of cost of clearing (if any), and of such other work as may be needed to make the ground available for interment. The position of graves (if any), on the land should be shewn, and the denomination of the deceased reported when practicable.

Letter reporting survey.

Designs of a few Cemeteries are shewn on diagram, *Appendix* X.

On the design of Cemetery No.1 it will be observed that there is a smaller area indicated by broken lines, which includes a part of each allotment; this smaller area, is that which it is intended to enclose by fencing, and prepare for interments, and which will probably be found sufficient for, say, ten years.

APPENDIX F. SURVEY MARKS.

Par 137.

No. 56, 1902. An Act to consolidate enactments relating to Survey Marks, official landmarks, and beacons (3rd September, 1902.)

BE it enacted by the King's Most Excellent Majesty, by and with the advice and consent of the Legislative Council and Legislative Assembly of New South Wales in Parliament assembled, and by the authority of the same as follows:-

- 1. This Act may be cited as the "Survey Marks Act, 1902.".
- 2. The Act sixteenth Victoria number fifteen is hereby repealed.
- 3.(1) In the conduct of official surveys made by the direction or under the authority of the Government, the distinguishing mark to be used by the Surveyors appointed or licensed by the Government to conduct the same shall be it the form of a broad arrow, which mark shall not be used by private surveyors or other persons not authorised in that behalf by the Government.

Short Title.

Repeal.

Private surveyor and others not to use official survey marks. 16Vic. No. 15,s. 1.

- (2) Every person who makes or uses such mark in marking any boundary or so as to appear to indicate a boundary of any land, except in the conduct of an authorised official survey, shall for every such offence, be liable to a penalty not exceeding ten pounds.
- 4.(1) If any person willfully obliterates, removes, or defaces any such survey mark as aforesaid or any landmark or beacon which has been erected by or under the direction of any officer of the Survey Department, or by a Surveyor licensee by the Government, such person shall for every such offence be liable to a penalty not exceeding ten pounds.

Penalty for unauthorized defacement or destruction of survey marks, landmarks, or beacons.

- (2) Nothing herein contained shall render the owner or occupier of any land liable to any penalty for the removal of any tree thereon upon which any such mark has been made which he may desire to remove in fencing, clearing, or otherwise improving such land.
- 5. Penalties under this Act may be sued for and recovered summarily before any two Justices in Petty Sessions by any person authorised in that behalf by His Majesty's Attorney-General.

Recovery of penalties. *Ibid.* ss. 1, 2.

APPENDIX G.

L.L.B. - 85. Par. 188

FORM FOR COMPUTATION OF AREAS.

Parish of County of

No. of		Reduced		Latitu	ıde.	Depart	ure.	Double	Double	Areas.
Traverse Line.	Bearing.	Bearing.	Distance.	North.	South.	East.	West.	Longitudes.	North.	South.

NOTE -

Offsets to be indicated here.

I hereby certify that the calculations and computations exhibited on this sheet are correct, and that the bearing and distances are derived from Field Notes taken by me in connection with the survey of the area shewn on plan of;

Portion Parish of County of accompanying my letter No......

(Signature) (Date)

Cat. No. of Plan

Par. 239.

L.L.B. - 78.

reporting

Land District of Mr Surveyor to the District Surveyor at

on portion No , parish of area county of 1. Date of inspection 2. Easiest accessible Railway Station, Port, Town, and Butter Factory, if any; distance therefrom, and cost of carriage thereto; description of roads. 3. Physical characteristics and geological formation; character of soil and subsoil. 4. (a) Natural water supply; if insufficient state - (b) what (a) facilities exist for obtaining or storing; (c) cost of (b) providing an adequate supply. (c) Size of necessary tank or dam cubic yards, at per yard, £ 5. Mean annual rainfall as supplied from records of inches at (This will be furnished by the Land Board Office). Government Astronomer. 6. Extent of land suitable for agriculture; whether in one or more parts; extent prepared for cultivation. 7. The most profitable kinds of cultivation, and probable, average yield per acre. 8. Most suitable class of fencing and cost 9. Character of pasturage, soundness of country; whether, Cost, £ per mile. fattening or breeding, and kind of stock for which it is adapted; state if suitable for dairying By whom effected, date, and 10. Improvements, description, Owner. Value. Value to incoming and position. by whom claimed. tenant 1 sheep to 11. Grazing capacity of land, in average seasons, as at acres; 1 head of large stock to present improved. acres. 12. Means by which grazing capacity can be further profitably increased, and cost of same. Total, £ 13. Average grazing capacity, when improvements 1 sheep to acres; 1 head of large stock to specified in preceding paragraph have been effected. acres. 14. Noxious animals, and estimated annual cost of coping with same. 15. Timber About acres of thick forest country, timbered with About acres of open forest country, timbered with About acres of plain country. (a) Ringbarking, suckering, &c. 16. Cost of preparing land for - (a) Grazing; (b) Agriculture (b) Green timber per acre. Dead timber per acre. 17. Suitability of timber for fencing and building purposes, and value of standing timber. Is its reservation or protection advisable; if so, state special conditions if any. (Sec. 4, Act, '05, and Sec. 21, Forestry Act, 1909). 18. Scrub About acres, consisting of of which are edible. 19. Particulars of authorised Mining Occupations 20. GENERAL REMARKS-

I hereby certify that this Report was prepared by me from notes taken on the ground.

19 Date

Page 54 of 102

D. S. O.		I	Land District							•••						
A	Account No.															
Head of Serv	vice - SURVEY OF LANDS Form	A. 9	New South Wales													
Pavabl	le from Vote of £	_		LAN	DS.	Item	No		of Ar	propriation	Act of 19 .					
•	vey					_			-		• • • • • • • • • • • • • • • • • • • •					
		UDVEVE CU	ADCED FOR DV I INI	DAN	E A CLIDE			•								
	mental Reference No															
From the	to the	roods		r the s	urvey an	a measurement o	Γ	• • • • •	• • • • • • • • •	• • • • • • • • • • • • • • • • • • • •	• • • • • • • • • • • • • • • • • • • •					
			perches .	Do	to of Sur	vey		10		For data	ile ego 4 th page					
	containing					•										
	of			County of												
Instructions	No of the	to		Pla	in with L	etter No		the	• • • • • • • • • •							
Cat No. Of Plan.	Class of Work	Quantity	Rate £. s. d.	Surveyor's Charge.		Survey as paid for by the Department.	Initial of Officer passing Account.	I	amount paid by partment.	No. of papers.	Remarks.					
	Boundaries of Portions, Reserves, or Leased Areas		at 0 0 9 per chain			at 9d.										
	Do do do do		" 0 0 6 "			" 6d.										
	Marked lines of Roads under Public Roads Act.		" 0 1 0 "			" 1/					 					
	Do do (not over 3 chains)		"009 " "006 "			" 9d.										
	Do do (over 3 chains)		" 0 0 6 "			" 6d. " 6d.										
	Features Connections		" 0 0 6 " 0 0 4½ "													
D. S. O.	Connections		" 0 5 0 each			472d. " 5/-										
Items examined	Do other		" 0 2 6 "			" 2/6										
	001		ŭ 2 ŭ			270										
19	Decreased					Decrease										
						Beerease										
Checked,	Local increase					Increase										
	Special Marks		" 0 2 6 each			at 2/6										
	Travelling with camp and equipment		" 0 1 0 per mile			" 1/-										
19	Comparison of azimuths		" 0 10 0 each service			" 10/-										
	Determination of magnetic variation		"100"			" 20/-										
	Total															
	 							ļ			 					
	Advance recommended as per advice No															
	Of19															
								ł	+							
	1			·	Balance		£									

DECLARATION.


I hereby, on honor, declare that I have faithfully and truly surveyed, measured, and marked out on the ground, the lines and corners for which I have charged in this Account, that the Plan herewith forwarded is correct, and the whole service has been performed with care, and in strict accordance with the regulations and practice of the Department of Lands.
Licensed Surveyor.
CERTIFICATE OF DISTRICT SURVEYOR. I certify that the Plan of the Survey herein charged for has been duly received, and the items as passed for payment in this Voucher are correct, and that the service has been performed in strict accordance with the regulations for the guidance of Licensed Surveyors and practice of the Department of Lands, and I recommend payment subject to deduction of amount already advised as an advance on account.
District Surveyor. St 3128
I certify that the amount charged in this Voucher as to computations, castings, and rates, is correct. Examined,

This is the form "A" for Accounts for surveys of lands for sale at Auction, for Conditional Sale, for sale in virtue of Improvements, for Conditional Lease, for Pastoral Lease, for Homestead Lease, Homestead Farm, Crown Lease, Suburban Holding, &c., and for Roads, Reserves, Features, and Connections.
The class of survey for which the account is rendered should, on each account, be stated in the place provided for that purpose. St 3128
NSW Department of Lands – Regulations for the Employment of Licensed Surveyors – 1914 Page 57 of 102

	1				2				3		4		5)	6 / 8		9			
Pe	rimeter at	9d.		I	Perimeter	at 6d.			Roads	at 1s.	Roads at	9d.	Roads	at 6d.	Features	s at 6d.	Connect		New	0.1 G
Por. No.	Chains.	Links.	Por. No.	Chains.	Links.	Por. No.	Chains.	Links.	Chains.	Links.	Chains.	Links.	Chains.	Links.	Chains.	Links.	Chains.	Links.	Corners.	Other Corners.
5	80*	00	5	7*	00								58	15	20	00	45	00	A	
		. 		55	00		<u> </u>						36	65	20	00		5	В	
				32	00								58	71	20	00			С	
				32	00								36	12					D	
				45	00					9			3						Е	
				10	00								-5						F (Old tr	ee and peg gone)
				15	00															
				8	00															
				7	00															
				6	00															
				42	60															
6	31	63				İ													G	В
	31	63																	Н	
	16*	74		14*	89	<u></u>													I	
7	31	63				<u> </u>				<u> </u>	35	00							K	Н
	31	63									Cosec. 1	03							L	I
	8	00				ļ														
8	24	00				<u> </u>					18						10	00	M	С
	32	00									16									D
											Cosec. 1	02								Е
					3	ļ		.5		ļ								A		
									Trovallin	a with a	ımp and equipme	ent in corne	action with	thic com	vica	mila	es, viz. :-			
						ļ			Haveilli	ig with Ca	mp and equipme	ant in coille	cuon with	i uns ser	vice,	111116	55, VIZ. :-			
									F	rom Port	ion No.	Parish	of				Count	y of		
									Т	o Portion	ı No.	Parish	of				Count	y of		

- 1. For the measurement and marking of the first 80 chains of boundary of each portion.
- 2. For the remainder of the measurement and marking of the boundaries of each portion.
- 3. For roads under Public Roads Act, including cosecants.
- 4. For roads reserved through portions not over 3 chains wide, to be marked on both sides at £3 per mile of road, to be paid for by the traversed side, including cosecants.
- 5. For roads and driftways reserved through portions exceeding 3 chains in width, to be marked on both sides, and each side to be paid for, including cosecants.

- 6. For ranges and watercourses, water-races, coastline and features.
- 7. For connections between portions, &c.
- 8. For new corners, to be specified by letters corresponding with plan.
- 9. For other corners, to be similarly specified.



	D. S. O.							APPEN	DIX	Ib			Par. 237.
Account No		I	Land District									•	
Head of Ser	vice - SURVEY OF LANDS Form	ı A <u>9</u>	<u> New South Wales</u>										
Payab]	e from Vote of £	for the I	DEPARTMENT OF	FLAN	DS.		Item	No	of	App	ropri	ation Act	of 19 .
	vey										_		
v	•	URVEYS CH	HARGED FOR BY LIN	ERA M	(EASU)	REM							
From the	mental Reference No	CRVETS CI	Fo	r the s	urvev	and	measurement o	f					
	Acres	roods		1 1110	, (11 , (2)	uno		1		••••		• • • • • • • • • • • • • • • • • • • •	•••••
	containing	:	:	Da	ate of S	Surv	ey		19			For detai	ils see 4 th page.
	of												
Instructions	No of the	to		Pla	an with	ı Le	etter No	of	f the .				
Cat No. Of Plan.	Class of Work	Quantity	Rate £. s. d.	Surveyor's Charge.			Survey as paid for by the Department.	Initial of Officer passing Account.	Amount paid by Department.		Ŋ	No. of papers.	Remarks.
	Boundaries of Portions, Reserves, or Leased Areas		at 0 0 9 per chain		1 1		at 9d.	Account.					
	Do do do do do	\	"006"		<u> </u>		" 6d.						
	Marked lines of Roads under Public Roads Act. Do do (not over 3 chains)		" 0 1 0 " " 0 0 9 "		 		" 1/ " 9d.						
	Do do (not over 3 chains) Do do (over 3 chains)		"006 "		 		9a. " 6d.						
	Features	}	"006"		 		" 6d.		b				
	Connections		" 0 0 4½ "] <u> </u>		" 4½d.						
D. S. O.	Corners new		" 0 5 0 each " 0 2 6 "		 		" 5/- " 2/6						
Items examined	Do other	 	0 2 0				2/0						
		\			 								
19	Decreased						Decrease						
	7 1:	 		<u> </u>	 		· · · · · · · · · · · · · · · · · · ·						
Checked,	Local increase Special Marks		" 0 2 6 each		 		Increase at 2/6						
	Travelling with camp and equipment		" 0 1 0 per mile	I	 -		" 1/-		·				
19	Comparison of azimuths		" 0 10 0 each service	I	1		" 10/-						
	Determination of magnetic variation		"100"				" 20/-						
	T . 1												
	Total				 								
				1	† <u> </u> -								
	Advance recommended as per advice No		1		11_								
	Of19				ļ								
]	Balanc	e		£					

DECLARATION.

I hereby, on honor, declare that I have faithfully and truly surveyed, measured, and marked out on the ground, the lines and corners for which I have charged in this Account, that the Plan herewith forwarded is correct, and the whole service has been performed with care, and in strict accordance with the regulations and practice of the Department of Lands.
Licensed Surveyor.
CERTIFICATE OF DISTRICT SURVEYOR. I certify that the Plan of the Survey herein charged for has been duly received, and the items as passed for payment in this Voucher are correct, and that the service has been performed in strict accordance with the regulations for the guidance of Licensed Surveyors and practice of the Department of Lands, and I recommend payment subject to deduction of amount already advised as an advance on account.
District Surveyor St 3128
I certify that the amount charged in this Voucher as to computations, castings, and rates, is correct. Examined,

NSW Dept of Lands Regulations for Licensed Surveyors 1914
This is the form "A" for Accounts for surveys of lands for sale at Auction, for Conditional Sale, for sale in virtue of Improvements, for Conditional Lease for Pastoral Lease, for Homestead Lease, Homestead Farm, Crown Lease, Suburban Holding, &c., and for Roads, Reserves, Features, and Connections.
The class of survey for which the account is rendered should, on each account, be stated in the place provided for that purpose. St 3128
NSW Department of Lands – Regulations for the Employment of Licensed Surveyors – 1914 Page 62 of 102

1			Z						3 4				3 0					ð	9	
Perimeter at 9d.			Perimeter at 6d.					Roads at 1s.		Roads at 9d.		Roads at 6d.		Features at 6d.		Connections at 4½d.		New		
Chains.	Links.	Por. No.	Chains.	Links.	Por. No.	Chains.	Links.	Chains.	Links.	Chains.	Links.	Chains.	Links.	Chains.	Links.			Corners.	Other Corners.	
		,																		
109	00				<u> </u>															
					<u> </u>															
			ļ				ļ							9		5	61	A	32	
			ļ		ļ										ā					
																		D		
							ļ													
															ā					
					ļ															
					ļ															
					ļ										9					
			<u> </u>		.							ļ	!							
					1								1							
					ļ															
					1								1							
					ļ															
								Travelling with camp and equipment in connection with this service, miles, viz. :-												
								From Portion No. Parish			sh of				Count	County of				
								To Portion No. Parish o			ish of County of					ty of				
	imeter at	Chains. Links.	Chains. Links. Por.	Chains. Links. Por. No. Chains.	Chains. Links. Por. No. Chains. Links.	Chains. Links. Por. No. Chains. Links. Por. No.	Chains. Links. Por. No. Chains. Links. Por. No. Chains.	Chains. Links. Por. No. Chains. Links. Por. No. Chains. Links.	Travellin	Chains. Links. Por. No. Chains. Links. Por. No. Chains. Links. Chains. Links. 109 00	Chains, Links, Por. No. Chains, Links, No. Chains, Links, Chains,	ineter at 9d. Por No. Chains Links Por No. Chains Links Por No. Chains Links Chains L	Inter at 9d. Port Port	ineter at 9d. Chains, Links, Por. No. Chains, Links, C	imeter at 9d. Chains. Links. Por. No. Chains. Links. Por. No. Chains. Links. Por. No. Chains. Links. Por. No. Chains. Links. Chains. Lin	imeter at 9t. Port Chains Links Port No. Chains Links Port No. Chains Links Chain	Chains Links Port Chains Links Port Chains Links Link	Chains Links Port Chains Links Port Chains Links Links	No. Chains Links Port No. Chains Links Ch	

1. For the measurement and marking of the first 80 chains of boundary of each portion.

2

- 2. For the remainder of the measurement and marking of the boundaries of each portion.
- 3. For roads under Public Roads Act, including cosecants.
- 4. For roads reserved through portions not over 3 chains wide, to be marked on both sides at £3 per mile of road, to be paid for by the traversed side, including cosecants.
- 5. For roads and driftways reserved through portions exceeding 3 chains in width, to be marked on both sides, and each side to be paid for, including cosecants.


- 6. For ranges and watercourses, water-races, coastline and features.
- 7. For connections between portions, &c.
- 8. For new corners, to be specified by letters corresponding with plan.
- 9. For other corners, to be similarly specified.

6

See Paragraphs 222 & 223

Diagram to illustrate Scale of Fees Viz: for measurement of

TOWN ALLOTMENTS



Drawn and Printed at the Department of Lands, Sydney, N.S. W. 1914

		11011 DC	pt of Lanas Regards	10115 101 1		ou builtejois ibi					
D. S	S. O.	•	_		Par. 237.						
Account No		I	Land District								
Head of Ser	vice - SURVEY OF LANDS Form	1 A.	New South Wales								
	le from Vote of £	-		LANDS	3	Item	No	of	Annronri	iation Act	of 19
•		101 the 1	DEITHOTIVIETOT		•						
	vey			ED 1 3 EE 1	GI ID EL						
Depart	mental Reference No	URVEYSCH	IARGED FOR BY LINI	ERA MEA	SUREN	ANT. [Sub-Head or	Estimate	• • • • • • •	• • • • • • • • • • • • • • • • • • • •		
From the	to the			r the surv	vey and	l measurement o	t	• • • • • •	• • • • • • • • • • • • • • • • • • • •	• • • • • • • • • • • • • • • • • • • •	• • • • • • • • • • • • • • • • • • • •
l	Acres	roods	perches	ъ.	CO			10		г 17	•1 4th
	containing					/ey					
Parish	of	• • • • • • • • • • • • • • • • • • • •	•••••	Coun	ty of		• • • • • • • • • • • • • • • • • • • •		• • • • • • • • • • • • • • • • • • • •		• • • • • • • • • • • • • • • • • • • •
Instructions	No of the	to		Plan	with Le	etter No	of	f the .			
Cat No. Of Plan.	Class of Work	Quantity	Rate £. s. d.	Surve Chai	,	Survey as paid for by the Department.	Initial of Officer passing Account.	Amount paid by Department.		No. of papers.	Remarks.
	Boundaries of Portions, Reserves, or Leased Areas		at 0 0 9 per chain			at 9d.					
	Do do do do do		"006"			" 6d.					
	Marked lines of Roads under Public Roads Act.		" 0 1 0 "			" 1/					;
	Do do (not over 3 chains) Do do (over 3 chains)		"009 " "006 "			" 9d. " 6d.					[
	(**********************************		"006 "			6d. " 6d.					
	Connections		" 0 0 0 " " " " " " " " " " " " " " " "			" 4½d.					
D. S. O.	Corners new		" 0 5 0 each	 		" 5/-					
Items examined	Do other		" 0 2 6 "			" 2/6					
	1		1								,
	1		1								
19	Decreased			i	Ì	Decrease					.
	1										,
Checked,	Local increase	î				Increase					
	Special Marks		" 0 2 6 each			at 2/6					<u></u>
	Travelling with camp and equipment		" 0 1 0 per mile			" 1/-					<u> </u>
19	Comparison of azimuths		" 0 10 0 each service			" 10/-					}
	Determination of magnetic variation	l	"100"		1	" 20/-					i

Total

Advance recommended as per advice No.

Of19......

Balance

£

DECLARATION.

I hereby, on honor, declare that I have faithfully and truly surveyed, measured, and marked out on the ground, the lines and corners for which I have charged in this Account, that the Plan herewith forwarded is correct, and the whole service has been performed with care, and in strict accordance with the regulations and practice of the Department of Lands.
Licensed Surveyor.
CERTIFICATE OF DISTRICT SURVEYOR. I certify that the Plan of the Survey herein charged for has been duly received, and the items as passed for payment in this Voucher are correct, and that the service has been performed in strict accordance with the regulations for the guidance of Licensed Surveyors and practice of the Department of Lands, and I recommend payment subject to deduction of amount already advised as an advance on account.
District Surveyor St 3128
I certify that the amount charged in this Voucher as to computations, castings, and rates, is correct. Examined,

NSW Dept of Lands Regulations for Licensed Surveyors 1914
This is the form "A" for Accounts for surveys of lands for sale at Auction, for Conditional Sale, for sale in virtue of Improvements, for Conditional Lease, for Pastoral Lease, for Homestead Lease, Homestead Farm, Crown Lease, Suburban Holding, &c., and for Roads, Reserves, Features, and Connections.
The class of survey for which the account is rendered should, on each account, be stated in the place provided for that purpose. St 3128
NSW Department of Lands – Regulations for the Employment of Licensed Surveyors – 1914 Page 67 of 102

<u> </u>			2					3 4			5 6				7	<u></u>	8	9			
Perimeter at 9d.		9d.	Perimeter at 6d.					Roads at 1s.		Roads at 9d.		Roads at 6d.		Features at 6d.		Connections at 4½d.		New	Other Commen		
Por. No.	Chains.	Links.	Por. No.	Chains.	Links.	Por. No.	Chains.	Links.	Chains.	Links.	Chains.	Links.	Chains.	Links.	Chains.	Links.	Chains.		Corners.	Other Corners.	
5	35	00	5	17	00								1						G	M	
																			Н	N	
																				N (new peg)	
																				G	
														ļ						H	
6	30	00		17	00														I	H	
	-				1									-			İ			M	
																				O	
														_						H	
7	79	00		20	00										25	00			С	В	
,				20											23	- 00			D	E	
	<u>-</u>				<u> </u>			<u> </u>						-						C	
														-						D	
8	80	00		6*	00										27	00			A	В	
				20	00														F	Е	
																				A	
														_						F	
														_							
																					
									Travellin	g with ca	amp and equipme	ent in conne	ection with	n this ser	vice,	mile	es, viz. :-				
									F	rom Port	tion No.	Parish	of				Count	nty of			
									To Portion No. Parish of				of		County of						

Page 68 of 102

- 1. For the measurement and marking of the first 80 chains of boundary of each portion.
- 2. For the remainder of the measurement and marking of the boundaries of each portion.
- 3. For roads under Public Roads Act, including cosecants.
- 4. For roads reserved through portions not over 3 chains wide, to be marked on both sides at £3 per mile of road, to be paid for by the traversed side, including cosecants.
- 5. For roads and driftways reserved through portions exceeding 3 chains in width, to be marked on both sides, and each side to be paid for, including cosecants.


- 6. For ranges and watercourses, water-races, coastline and features.
- 7. For connections between portions, &c.
- 8. For new corners, to be specified by letters corresponding with plan.
- 9. For other corners, to be similarly specified.

Appendix" Is"

See Paragraphs 62 & 231

Diagram to Illustrate Scale of Fees

VIZ: FOR SUBDIVISION OF MEASURED PORTIONS



The Diagram shews the subdivision of Four measured portions Nº\$1.2.3 & 4.

Drawn and Printed at the Department of Lands, Sydney, N.S. W. Sept 1914

D. S	. O.					NSW D	ept of Lan	ds R	egu]	latio	ons for Lic		-	s 1914 DIX Id.						
Account	No.						Land Dist	rict.												
Head of	Serv	vice - S	URV	EY OF LANDS.	- Forn	n B.	New Sout	h Wa	ıles											
Pa	vabl	e from	Vote	e of £		for the	DEPART	MEN	NT (OF I	LANDS.]	Item No	oo	f Ap	proi	priat	tion Act	of 190 .
	<i>J</i>													_		-		•		
[Departm	ental	Referen	ce No				SPE	CIAL	SEF	RVIC	CES.		~			-				St 1326
Instructions. Diary. From the to the 19 For the undermentioned Services, viz. :-			oned	Field Office			Time allowed	l by the Depa	artment.	Officer	Date and No.	Amount paid by the		No. of	Remarks					
Date.	No.	Month.	Day.	Particulars of Service.	Area.	Field – No. of days.	Office – No. of days.	Aı	noun	t.	Field – No. of days.	Office – No. of days.	Area.	passing Account.	passing Transmission		Department.		Papers.	
			<u> </u>		ļ		<u> </u>	£	s.	d.			ļ			£	s.	d.		
			ļ		<u> </u> 				ļ				ļ					 		
			 	 	 				ļ				ļ					 		
		i 	<u> </u> 	<u> </u>	 		<u> </u> 		 	ļ		 	<u> </u>					 		
		 	<u> </u>		 				 				 				 	 		
		 		<u></u>			<u> </u>						 					<u> </u>		
									ļ											
	ļ		ļ 	 	ļ		ļ ļ		ļ	ļ 		 	ļ 					ļ		
	ļ		<u> </u>		ļ 		<u> </u> 		ļ	ļ		 	ļ 					ļ		
		 	ļ 		ļ		<u> </u>		ļ	ļ		 	ļ 					<u> </u>	<u></u>	
		 	<u> </u>		ļ		<u> </u>		<u> </u>	ļ		 	<u> </u>					<u> </u>		
			<u> </u>	 	<u> </u>		<u> </u>		 			 	<u> </u>					 		
			 	ļ	 				 				 				+	 		
	1		<u> </u>		<u> </u>		 		 			}	- 					 		
							† 					 								

Balance

DECLARATION.

I hereby, on honor, declare that I have faithfully performed the service charged for in this Account, the plan and report herewith forwards the whole service performed with care, and in strict accordance with the Regulations and practice of the Department of Lands. I further, on hon number of days charged for were actually expended on the work referred to, and that on each day charged for I was fully employed on the work	nor, declare that the
Lic	censed Surveyor.
CERTIFICATE OF DISTRICT SURVEYOR. I certify that the items passed for payment in this Voucher are correct, that the plan and report have been duly received, that the service h in strict accordance with the Regulations for the guidance of Licensed Surveyors and practice of the Department of Lands, and I accordingly re of the account for the amount passed by me as shown.	
	District Surveyor
I certify that the amount charged in this Voucher as to computations, castings, and rates, is correct. Examined	

(See also Appendix V.) APPENDIX J.

Par 206

AUTHORISED ABBREVIATIONS OF WORDS ON MAPS.

A 1111			3.6
Addition	Ad.	Magnetic	Mag.
Administrator	Admor.	Maximum	Max.
Agricultural	Ag.	Measurement	Meast.
Altitude	Alt.	Mechanic	Mech.
Applicant	App.	Memorandum	Memo.
Approved	Appd.	Meridian	Mer.
Approximate	Approx.	Methodist	Meth.
Association	Assoc.	Metropolitan	Metrop.
Astronomical	Astro.	Military	Mil.
Australian	Aust.	Minimum	Min.
Azimuth	Az.	Ministerial	Minl.
Bank	Bk.	Miscellaneous	Misc.
Baptist	Bap.	Mount	Mt.
Boundary	Bdy.	Municipal	Mu.
Bridge	Br.	Navigable	Nav.
Business	Bus.	Number	No.
Cardinal Points	(See Note)	Occupation	Occ.
Catalogue	Cat.	Occupier	Occ.
Cemetery	Cemy.	Original	Or.
Central	Cent.	Old Roll	o. r.
Centennial	Centen.	Paddock	Pad.
Certificate	Cert.	Parish	Par.
Chain	Ch.	Parliament	Parlt.
Church	Ch.	Pastoral	Past.
Church of England	Ch. E.	Permanent	Permt.
Common	Com.	Place	PI.
Company	Co.	Platform	Plt.
Confirmed	Confd.	Point	Pt.
Condition	Con.	Population	Pop.
Conservation	Conserv.	Portion	Por.
County	Co.	Post Office	P. O.
Creek	Ck.	Pre-emptive	Pre.
Crown Lands Act	C.L. Act	Presbyterian	Presbyt.
Declination	Dec.	Private	Priv.
Dedicated	Ded.	Proclamation	Procl.
Department	Dept.	Proposed	Pro.
Distance	Dist.	Public	Pub~
District	Dist.	Purchase	Pur.
Division	Div.	Purpose	Ppse.
Electorate	Elect.	Per original	p. o.
Elongation (star)	Elong.	Railway	Ry.
Environs	Envs.	Recreation	Rec.
Examined	Exd.	Reference	Ref.
Executive Council	Ex. Co.	Register	Regr.
Executors	Exors.	Regulation	Reg.
Exclusive	Excl.	Reserve	Res.
Extension	Exten.	Residence	Res.
Folio	Fol.	River	Riv.
Foot	Ft.	Road	Rd.
Forest	Fo.	Roll (plan)	r.
Gazette	Gaz.	Roman Catholic	R.C.
General	Gaz. Gen.	Saint	St.
Geographical	Gen. Geo.	School	Sch.
Governor	Gov.	Section	Sec.
Government	Govt.	Senior	sen.
Grant	Gt.	Settlement	Set.
Great Northern Railway	G.N. Ry.	Sheet	Sh.
Great Southern Railway	G.N. Ry. G.S. Ry.	Society	Soc.
Sieur Soumern Ranway	0.5. Ky.	Dociety	500.

Court Western D. '1	CWD	Ctation	Ct
Great Western Railway	G.W. Ry.	Station	Stn.
Heliograph	Helio.	Steam Ship	S.S.
Horticultural	Hort.	Street	St.
Hospital	Hosp.	Suburban	Sub.
House	Ho.	Swamp	Sw.
Improvement	Impt.	Telegraph	Tel.
Inclusive	Incl.	Temporary	Temp.
Independent	Indep.	Town	Tn.
Individual	Indiv.	Traverse	Trav.
Institute	Inst.	Trigonometrical	Trig.
Irrigation	Irr.	Unnecessary	Un.
Island	Isl.		
Junior	Jun.	Variation	Var.
Latitude	Lat.	Village	Vill.
Leasehold	Lhold.	Volume	Vol.
License	Lic.	Wesleyan	Wes.
Link	Lk.	Wharf	Whf.
Lithograph	Litho.		
Longitude	Long.		
Limited	Ltd.	Yards	Yds.

Note. - It may be pointed out that, of these abbreviations, many are intended to apply to various changes of a word -e.g. "App." for, applicant, application, applied for; "Occ." for occupier, occupation; and others apply to several words e.g. "Co." for County, Company, Council. It is held that the context should enable the sense to be perceived.

As to the Cardinal points, the letters significant thereof are N., S., E., and W., and these should generally convey the sense required; otherwise if the adjective must be used, it should be written in full, thus - Northern.

As a general rule, the full names of Grantees should be written; but when there is insufficient space, the recognised abbreviations may be used, and initial letters should be used only where there may be several pre-nomina. *16083 - H

APPENDIX K.

RETURN for the Month of , by Surveyor, containing Statement of Unfulfilled Instructions, Report of Progress, and proposed Course of Duty.

Instruc	ctions.		Report of	of Services Perfo	rmed		
No.	Date.	Purpose of Measurement or Applicant.	Area.	Parish No. and Name.	County.	Date and No. of Letter of Transmission.	Remarks.

REPORTOF PROGRESS

To the District Surveyor at	(Signature)
	(Date)
STATEMENT of Proposed Course of Du	ty for the Month of.

STATEMENT of Unfulfilled Instructions in the hands of Mr.

, Surveyor, on the 1st

	Instruction	ıs.		Particulars of Instructions.		Remarks		
•	Marginal No	No.	Date	Purpose of Measurement or Applicant	Area.	Parish or Locality.	Date Survey Finished.	General.
•								

DIRECTIONS TO BE OBSERVED IN COMPLETING THIS FORM OF RETURN.

THIS Return is to be forwarded to the District Surveyor on or before the third day of the month. All unfulfilled instructions are to be quoted on the proper page, and in the column headed "Marginal No." the registration number of the paper is to be inserted. Instructions which are incomplete, *e.g.*, surveys effected, the plans of which have not been drawn, or are being prepared, should be quoted as unfulfilled, the state of the business being noted under "Remarks," *e.g.*, land measured, plan not drawn, &c.

NSW Dept of Lands Regulations for Licensed Surveyors 1914 APPENDIX L.

RETURN OF FENCING.

Par. 196-199

MEMORANDUM, showing the names of the Owners or reputed Owners of the enclosed Lands through which the road passes the length of new fencing required to be erected within each enclosure, and the cost thereof. Also, the length of the existing fences which will require removal, and the cost of their re-erection.

Name of Owner or		Length of Fo	encing Required.		
Reputed Owner.	Name of Occupier.	New.	Old (to be Renewed and	Cost per Rod.	Total Cost.
Reputed Owner.			Re-erected).		
		Chains	Chains		

Form A.

SCHEDULE OF PROPOSED RESUMPTION UNDER THE PUBLIC ROADS ACT, 1902.

DESCRIPTION of the Lands proposed to be resumed in connection with County of , Parish of

, Land District of

, Shire

Po	rtions of Land A	ffected					Area t	to be Res	umed	
No. of Portion.	Area. of Portion.	Parish.	Grantee or Reputed Owner.	Occupier.	Character of Holding.	Width of Land to be Resumed.	a.	r.	p.	Remarks.
	or r or work									
			(For resumptions of	flands and closing of ro	ads "Form B" Schedule	is to be used.)				

Copy to be sent to the Land Agent at

Pars. 196-199.

Form B.

SCHEDULE OF PROPOSED RESUMPTIONS AND WITHDRAWALS, ALSO OF ROAD RE-MARKED, AND OF ROADS, PROPOSED TO BE CLOSED UNDER THE "PUBLIC ROADS ACT, 1902."

Re-marked Road, with parts of existing Roads, are to be declared Public Roads.

DESCRIPTION of Lands proposed to be resumed and withdrawn, also of re-marked road, and of Roads deemed to be unnecessary which are to be closed in connection with the proposed part of road from Yass to Goulburn, and branch road towards Collector.

Parish of Goulburn, County of Argyle, Mulwaree Shire, Land District of Goulburn, Land Board District of Goulburn.

	ns of land ected.		3, 1, 3, 1,		Chanatanaf	Width in links of		rea to b	_	
No. of Portion.	Area of Portion in acres.	Parish.	Reputed Owner.	Occupier.	Character of Holding.	land to be resumed or withdrawn.		sumed of thdraw r.		Roads to be closed, &c.
7	40	Goulburn		Reserved road						This is a re-marking of reserved road 100 links wide which forms part of road from Yass to Goulburn.
										The unnecessary part of confirmed road within portion 105, west of the south-eastern prolongation of proposed road is to be closed, and will vest in the owner of the adjoining lands.
12	40	do	Edgar Jones	Edgar Jones	Freehold	Variable	2	0	0	The 2 acres are to be resumed as severed land.
12	40	do	do	do	do	100	1	0	0	The unnecessary part of reserved road within portion 12 is to be closed, and together with an area of 2 acres 3 roods of Crown lands (part of water reserve 297) lying between portion 12 and proposed road, is to be granted in compensation.
29	40	do	Bank of New South Wales	P. Gregory	C.P. 90-786	100	2	1	20	The unnecessary reserved road within portion 29 is to be closed and added to that portion, the area of portion and C.P. 90-786 to be reduced to 37 acres 3 roods. The unnecessary reserved roads within portions 21 and 22 are to be closed and added to those portions, the areas thereof to be increased to 35 acres and 31 acres, respectively, and area of C.P. 79-84 to 66 acres.
54	40	do	Wm. Edwards	Wm. Edwards	Pt. H.S. 08-74 of 90 acres	100		0 udes pa nch roa		This area to be withdrawn. The unnecessary boundary road separating portion 54 from part of portion 10 is to be closed and added to portion 54, the area of portion and H.S. 08-74 to remain unaltered.

	ns of land ected.				Character of	Width in links of	Area to be resumed or	
No. of Portion.	Area of Portion in acres.	Parish.	Reputed Owner.	Occupier.	Holding.	land to be resumed or withdrawn.	withdrawn. a. r. p.	Roads to be closed, &c.
97	40	Goulburn	Frank Booth, junior	Frank Booth, junior.	C.P.L. 10-59	100	2 2 10 (includes part of branch road.)	The unnecessary reserved road within portion 97, and unnecessary parts of boundary road separating portion 97 from parts of portions 10 and 102 are to be closed and added to C.P.L. (10-59), portion 97, the area thereof to be increased to 40 acres 3 roads. The unnecessary boundary road on the east of portion 100, and reserved road within that portion are to be closed and added thereto, the area of the portion and C.P. 07-109 to be increased to 63 acres 3 roads.
102	80	do	John Toomey	J. Toomey.	H.S. 00-54, Hom. Grant	100	2 1 0	This area to be withdrawn.
95	40	do	Michael Jones	M. Jones.	Part S.L. 07-56 of 120 acres	100	1 2 0 (Part of branch-road.)	This area to be withdrawn.
101	60	do	Frank Booth	F. Booth.	Freehold	100	3 2 20 (Part of branch road.)	The unnecessary parts of reserved road within portion 95 are to be closed and added to that portion, the area thereof to be increased to 40 acres 2 roods; also the unnecessary part of boundary road separating portion 96 from parts of portions 15 and 16, is to be closed and added to portion 96, part of same S.L. The area thereof to be increased to 42 acres, and that of the whole S.L. 07-56 to 122 acres 2 roods ex. road.
99	60	do	Oscar Bremner	O. Bremner.	C.L. 5,230	100	0 1 6 (Part of branch road.)	The unnecessary boundary roads separating portion 99 from parts of portions 16 and 17, and from part of portion 107 (west, of branch road) are to be closed and added to portion 99, the area thereof and area of C.L. 5,230 to be increased to 64 acres 3 roads.
107 (Priva subdi	100 ately vided)	do	P. Halloran (Representative of Dudley Estate)	Private subdivision road	Freehold	100	2 1 0 (Part of branch road.)	This area embraces private subdivision road. The remarked road and all parts of existing roads necessary to preserve the continuity of proposed roads are to be declared to be public roads.

NSW Dept of Lands Regulations for Licensed Surveyors 1914 APPENDIX O.

Pars. 196-199

PAPERS			Ε	O.S.60
I ow	ner of Portion	No		in the
Parish of				
in. the County of		do hereby	express my	
willingness to allow the land marked out for a road	by Mr		, Surv	eyor,
within the portions specified, to be resumed under	the Public Roads A	ct, 1902; an	d undertake t	:hat
no claim or compensation shall be made to the Cro	wn in respect there	of.		
(Name of Owner)				
(Witness)				
(Date)				

NSW Dept of Lands Regulations for Licensed Surveyors 1914 APPENDIX P.

Par. 87.

Topographical SURVEY OF COUNTRY FOR SETTLEMENT.

The object to be aimed at in these Topographical Surveys is to make such a delineation of the various classes of land, features, &c. that designs for subdivision and questions as to the suitability of the land for settlement, &c., can be prepared and answered without further inspection.

Object of survey

In order to secure uniformity in carrying out the surveys, and to ensure that the information so obtained may be readily available, the following directions are to be observed:-

The area to be surveyed should be inspected with a view to preparing a scheme for conducting operations to the best advantage.

Field operations.

Where there are no existing surveys which can be utilised as bases for the work, rapid theodolite traverses should be run to form backbones to which subsidiary work can be tied. The traverses should be from 5 to 7 miles apart - of course such distance may be increased or decreased at the discretion of the District Surveyor.

The details of the country inspected should be filled in from traverses made by compass or plane table in conjunction with either wire, wheel, or pedometer measurement, or pacing. These traverses should be connected with the backbone traverse or traverses, or with existing surveys.

The limits of the survey should, when practicable, follow fences, features, or tracks; and, in convenient positions, suitable marks should be left for the purpose of starting points or connections for further similar survey.

At any points where traverse lines touch surveyed lines, and also along the traverse lines themselves at suitable intervals, trees should be marked by cutting letters (alphabetically) about 2 feet in length out of the bark, and blazing the bark on the opposite side to the marking. Upon plan of survey should be indicated the kind of tree and aspect towards which the marking faces, *e.g.*, "Gum A east."

Approximate heights shall be observed at intervals by means of an aneroid barometer in order to illustrate the contour of the country. The observations should be made as far as possible at extreme points of elevation or depression.

In addition to the features and information usually depicted and noted, the limits of the following classes of land are to be located:-

First-class agricultural land.

Second-class agricultural land.

First-class grazing land.

Second-class grazing land.

Land on which standing timber should be conserved.

Land which should be reserved for Forestry purposes.

Closes are not to be calculated. It will be sufficient if the traverses can be made to close by plotting, and for this purpose they may, if necessary, be swung into position.

Accuracy

Plan

The plan should be drawn to a scale of 20 or 40 chains to the inch at the discretion of the District Surveyor. A finished plan is not required, all that is necessary is a working plan on which the requisite information is clearly shewn. The lengths and bearings of traverse lines need not be recorded on the plan. Backbone traverses are to be shewn by red lines and circles, other traverses by blue lines and circles, observed lines by broken blue lines, and designed roads by broken or dotted black lines.


Descriptions of country, timber, geological formation, &c., are to be written plainly on plan. The following colours are to be used; First-class agricultural land	Colours
In the North Coast district where dairying and allied industries are prominent factors in dealing with the question of settlement, the grazing country should be classified as follows; First-class	North Coast district.
The colours to be used for these are as follows; First-class Red edging. Second-class Blue edging. Third - class Broken blue edging Fourth-class Purple edging	
Information on the following points should be shewn on the plan in the respective areas by abbreviations, as here under indicated: Value of ringbarking and clearing effected per acre	Abbreviations
The Report should deal with :- Situation and distance from railway, town, or port. Means of access. Probable cost of clearing and forming roads. Rainfall, water supply, and facilities for water conservation. Character of the country. Purposes for which the land is adapted. Improvements and values. Areas necessary for home maintenance, and value of land. (a) With existing means of communication. (b) By providing railway communication. Timber. Land which should be reserved in the public interest. Any special matter not included in the foregoing that may come under notice during the survey.	Report


APPENDIX Q.


CERTIFICATE OF SURVEY OF LAND FOR


I,	,	a licensed Surv	eyor of Nev	v South Wales, h	ereby	certify	that
the land measured by	me; being					the p	olan of
which is transmitted	to the Departme	ent of Lands un	der cover of	my letter dated			, No.
is a part of							
I further state that the	ere is no encroac	chment of the s	aid land; and	d that upon inqui	ry I an	n infor	med
that there have not be	een any Easemen	nts acquired ov	er the same.				
Dated at	this	day of		A.D.			
				(Sig	gnatur	e)	


Sydney: William Applegate Gullick. Government Printer.-1915.











SURVEY REGULATIONS 1914

See Paragraph 176

	used on map	08.
State		+_+
Territorial Division	•	
	(Surveyed	>c −\$->c −\$->c −\$->c -\$->c
Pastoral Holding	Unsurveyed	
do. Dividing Line	Unsurveyed	
County	, , , , , , , , , , , , , , , , , , ,	
011	(management of the control of the co	
n // 000 / / ·		
0//		
/ / 0:		
	al Sale within a Gold Field	
	sale within a gold field	762 101 - 5h 15 151 151
- mail		
	it	
Reserve from Lease or		
	Lease or License	
	m Sale	
Classified Areas		2C — 2C — 2C — 2C
0/008///60 /1/608		
•		
	daries are coincident, such aud be delineated.	as County and Parish, the more
important shou		as County and Parish, the more
important shou Railway on las	ld be delineated.	as County and Parish, the more
important shou Railway on lai do. on sn	rge scale map	as County and Parish, the more
important shou Railway on lai do. on sn	rge scale map	as County and Parish, the more
Railway on las do on sn Public Road Surveyed Reserved Ro	rge scale map	as County and Parish, the more
Railway on las do. on sn Public Road Surveyed Reserved Ros Telegraph Line	rge scale map	
Railway on las do. on sn Public Road Surveyed Reserved Ros Telegraph Line	rge scale map	
Railway on las do on sm. Public Road Surveyed Reserved Ro. Telegraph Line When on a When not on	rge scale map	
Railway on las do. on sn Public Road Surveyed Reserved Ros Telegraph Line	rge scale map	
Railway on law do. on sm. Public Road Surveyed Reserved Road Telegraph Line When on a When not on Irack	rge scale map nall do. do. Boundary n a Boundary	ρ ρ ρ ρ ρ ρ ρ ρ ρ ρ ρ ρ ρ ρ ρ ρ ρ ρ ρ
Railway on law do. on sm. Public Road Surveyed Reserved Road Telegraph Line When on a When not on Irack	rge scale map	

SURVEY REGULATIONS 1914

FRS SIGNIFICANT OF HOLDINGS & RESERVES

	HOLD	INGS	
A.C.P.	Additional Conditional Purchase	M.P.	Mining Permit
A.H.L.	Additional Homestead Lease	M.R.	Miner's Right
An L.	Annual Lease	M.T.	Mining Tenement
AN.R.C.P.	Additional Non-Residential, Conditional Purchase	P.M.T.	Private Mining Tenement
A.W.L.	Artesian Well Lease	N.R.C.P.	Non-Residential, Conditional Purchase
B.L.	Business License	P.H.	Pastoral Holding
C.L.	Conditional Lease	P.W.P.	Public Watering Place
C.S.	Conditional Sale	P.S.	Public School
C.P.L.	Conditional Purchase Conditional Purchase Lease	R.A.	Resumed Area
CºL.	Crown Lease	R.L.	Residential Lease
D.P.	Deferred Payments	S.A.	Special Area
C.L.	Cold Lease	SCPL	Special Conditional Purchase Leas
P.C.L.	Private Cold Lease	S.P.C.L.	Special Private Gold Lease
H.F.	Homestead Farm	S.P.M.L.	Special Private Mineral Leas
HL	Homestead Lease	S.H.	Suburban Holding
H.S.	Homestead Selection	S.L.	Settlement Lease
I.A.H.	Irrigation Area Holding	Sc. L.	Scrub Lease
1.L.	Improvement Lease	So.L.	Snow Lease
INF.L.L.	Inferior Land Lease	Sp. L.	Special Lease
IP.	Improvement Purchase	SP	Special Purchase
LA.	Leasehold Area	T.L	Tank Lease
M.C.P.	Mining Conditional Purchase	V.L.O.	Volunteer Land Order
M.L.	Mineral Lease	W.L.L.	Western Land Lease
PML	Private Mineral Lease	AAP	After Auction Purchase
F.L.	Farm Lease (Church & School Lands)	P.L.	Pastoral Lease (Church & School La
0.L. ·	Occupation License	P.O.L.	Preferential Occupation License
O.L.		RVES	Ti ciei eliciai Occupation Erceno
			0.0 - 0 - 7/ 10
AR	Aboriginal Reserve	R.R.F.	Refuge from Flood Reserv
Auc. R.	Auction do.	R.R.	Railway do
C.R.	Camping do	T. Ç.	Temporary Common do.
F.R.	Forest do.	T.R.	Trigonometrical do.
G.R.	Old Government Reserve	T.S.R.	Travelling Stock do.
Q.R.	Quarry do.	V.R.	Village do.
R.P.B.	Public Buildings do.	W.R.	Water do. (Automatic Reserves on
Rec. R.	Recreation do	R. From S.&L.	Forfeiture and expiry
R. from Lse	Reserve from Lease	These abbreviation	ons are to be used only where ther
R. from Lee	do. from License	1	pace, otherwise the particulars are

do. from Occupation under Miner's Right and Business License.

Lithographed and Printed at the Department of Lands, Sydnoy N S W, 1974

NSW Dept of Lands Regulations for Licensed Surveyors 1914 Appendix"Wa" see paragraph 201 Conditional Turchase Licensed Surveyor (To be left clear for Registration No) to the District Surveyor at portion hansmitting plan of conditionally purchased by Noucher forwarddicher do 6. P. No At least one third margin -Dake No (see par 204) Cat. No Applied for Area applied for Sir, I have the honor to hansmit herewith Area measured. Survey fee haid & Survey fee haid & Do. Charted the Flan of portion of land containing numbered in the Farish of conditionally Examined Plan approved. purchased by under the Section of the Crown Lands Consolidation Act 1913, measured by me on accordance with Instructions No daled Here follows general report e.g. whether the applicants' starting point "was found on the ground NOTES and if so, how indicated on plan, or whether it was (a) Name of Land Office and Shire not found", Description of Land, Timber and Water Supply; Information as to Roads; Improvements, (6) Date of Survey specifying particulars of each ownership and date of completion; Included areas under Authorized (c) If within a Gold Field state name Mining occupation, if any, and Parts of boundaries which might be exempted from fencing I have the honor to be, Sir, Your obedient Servant, Licensed Surveyor

110 W Dept of Earl	55
	Appendix"W ^b " see paragraph 201
	Hienation
(To be left clear for Registration No)	Licensed Surveyor to the District Surveyor at hansmitting plan of portion measured for sale
negisnanon sr.	District Surveyor at
	hansmitting plan of portion measured
	jui suite
	(P)
	(Place)
(a)	(Dake) 191
$\mathcal{M}^{\mathcal{N}}$	No (see par 204)
M.	Sint
	I have the honor to transmit
	I with the bland of banking of
die i le i	nerewin me puun of junen of
At least one third margin	herewith the plan of portion of land containing
	numbered in
	the Parish of in
22	the Tarish of in within
lo lo lo lo lo lo lo lo lo lo lo lo lo l	the (b)
the second second	
3	
	measured by me on (c) in accordance with Instructions No
	accordance with Instructions N.
NOTES	dated
NOTES	Jestimate the value of the land
(a) Insert name of Land District	at per acre.
and Shire.	
(b) Name of Run and Name of	Here follows general report on conditions of land
Gold Field, if within either or both	
(c) Date of Survey.	
(d) Registration N. of papers enclosed.	report on improvements (if any) I. I.
	I have the honor to be,
	I have the honor to be, Six, Your obedient Servant,
	(Seamphuse)
	Licensed Surveyor

NSW Dept of Lar	nds Regulations for Licensed Surveyors 1914
To be left clear for	Appendix We"
	see paragraph 201.
Registration No	
	Conditional Lease
	0660
Licensed Surveyor	to the District Surveyor
Licensed Surveyor hansmitting/plan.of	acres applied for by as Conditional Lease No
nunsmirning fauncy	wies upgriewjordy
	as Conditional Lease No.
Land District of	
	(P_{1})
1.0	(Place)
At least one third margin	(Dak)
Noucher No	No (see par 204)
loucher s	Sir,
Advice forward	10 11 11 11
Mr 1 lid	I have the honor to hansmit herewith
Hucher forward	the plan of an area of acres, numbered
	in the Parish of
	1 1 0
	Country of measured
	by me on the
	by me on the for Conditional Lease No of the
A 1 No	Vondenonal Lease Ni of me
Cat. No	Land Dishict, applied for by
Area applied for	in withe of
Area measured	1.1. 100 1 16
Area maria	Conditional Purchase No being
Survey fee paid I	portion numbered in the Parish
Deincurredunder	
n 11 + £	of Country of
Regulations £	
	This Survey has been effected in accordance with Instructions No
	accordance with Instructions No
Charled	1 1 1
	dated ussued by the
Examined	District Surveyor issued by the
Plan approved	
JAMIN 17/	Thank hould be the little
4,500.00	I have also the honor to furnish the
	following information:-
	1. Objections to the Lease on the ground of Mining occupation or otherwise.
	accupanon or omerwise.

Remarks, including any necessary details respecting the survey.

Report on Form L.L. B. 18 forwarded herewith.

I have the honor to be,

Sir,

Your obedient Servant,

Signature

District Surveyor's Report to Chairman of Local Land Board!

	Improvement Turch	Appendix "W ^d " see paragraph 201.
(To be left clear for Registration . No)	Licensed Surveyor To the District Surveyor at transmitting plan of a portion of lan	
Papers (h) and plan herewith	Applied for by J. D. (6) at Vir (see par 20k) (Dake)	(c) 19
At least one third margin .	Thave the honor to hansmit , plan of a portion of land containing	herewith the
less slear	being alloment of section the Town of the (d) Gold in the Parish of	within Geld situated in the
20	the (d) Gold in the Parish of Country of to purchase by (e)	applied for
NOTES (a) Name of Gold Geld (b) Application Number	under the 62" Section of the Cro Consolidation Act 1913" and mean	sured by me
(c) Name of Sand Office (d) Name of Gold Gield (e) Name of Applicant as	in compliance with Instruction No. The improvements effected whom in respect of which the application for	(g) this land, and
in authorised occupation (1) Date of Survey (9) Viand date of Instruction (4) Registration Vid papers enclosed	Description of Improvements When Commenced Completed	Value £. s. d.
(i) Applicant or previous owner (j) Applicant or other person (k) Value per acre		
Weeks World		over /

- 6	BP.	60
- 10	N.	2.1
8	27	0 1

The improvements were inspected by me on the 19 ; I ascertained
The single within well snopeered sty me
on the 19; I ascertained
that they were made by (i)
and now belong to (i) I am of opinion that they were commenced
I am of opinion that they were commenced
and completed upon the dates specified
und singuesed ugan ine daves specified
All I I I I I I I I I I I I I I I I I I
At date of survey the applicant was
resident
I am of opinion the land above specified
is worth (k)
I have the honor to be
La la la la la la la la la la la la la la
M. O. I.
Sur, Your obedient Servant,
for the second s
Signature
Licensed Surveyor

NSW Dept of Lands Regulations for Licensed Surveyors 1914 Appendix We see paragraph 201 Licensed Surveyor to the District Surveyor at To be left clear for Registration No reporting on application for Improvement Rirchase Land District of Papers (9 No (see par 204) In compliance with instructions by your letter I have the honor to report on the character; value, and ownership of the improvements on allotment of section of the Town of situated in the Tarish of in the Country of under the 62" Section of the Grown Lands Consolidation Act 1913." NOTES Tinspected the above mentioned land on the (a) Application Number (b) Same of Gold Field certain improvements, which are the property of (c) Name of Land Office (d) Name of Gold Held (e) Same of Applicant as the particulars of which are as follows :in authorised occupation Description of Improvements Value (1) Date of inspection (9) Registered Nof papers enclosed (h) Value of land


At date of inspection the applicant was	
resident	
The land above specified was measured	
by and the plan	
was transmitted by his letter No	
10.	
A copy of the plan is herewith enclosed	٠
showing the improvements now reported I am of	
opinion that the allotment is worth	
Thave the honor to be,	
Sir, Your obedient Servant,	
Your obedient Servant,	
Signature	# W. A
Licensed Surveyor.	

NSW Dept of Lands Regulations for Licensed Surveyors 1914 Appendix X' Examples of Design for GENERAL CEMETERIES See Paragraph 95 3 NOTE The area which is sufficient for present use is indicated by broken lines. and Extension to Cemetery Plantation Plantation For 3 . 21 . 18 Reserve ROAD 100 WIDE Plantation GRAND PARADE THE 2 OXFORD ST. Church Unsectarian
3r. 20p. 5 Jews Unallotted of 301VA Unallotted England Presbyterian 1.0.0 Congregational 18.0.0 ILLAWARRA RD. 17.0.0 United Methodists MOORE ST. Church of England Church of England 8 2.0.17 20 Roman Catholic Presbyterian 7.3.28 ALLWAY ROAD 100 Methodist Roman Catholic 10 . 1 . 20 19.0.8

Brawn and Printed at the Department of Lands, Sydney, N.S.W. 1914.

Nº of Lith. /4.864.M.

 $NSW\ Department\ of\ Lands-Regulations\ for\ the\ Employment\ of\ Licensed\ Surveyors-1914$



NSW Dept of Lands Regulations for Licensed Surveyors 1914 Appendix "Z" (re Reg# 184) Papers Shire. PLAN OF Parish of County of Land District of Land Board District of Division. Reference to Traverse Reference to Corners Transmitted to the District Surveyor with my letter of Voucher Nº Passed Checked and Charted Examined Plan approved Chains to an Inch artment of Lands, Sydney, N.S. W. 1914 Scale Nº of Lith. 14. 666 M. Cat. Nº

NSW Dept of Lands Regulations for Licensed Surveyors 1914 (Par 200) PLAN of Connection between Portion 10_ Parish of Deepwater COUNTY GOUGH OF and Portion 14 __ Parish of Clevedon COUNTY SANDON OF S Holdin William Crommelin 40 ac 0 Marowan Holding omo 0 Mount Adra Trig: Station Boyd Holding o'Holding W u 315 10 gum 16 lhs A Reference to Special Marks 0 43'15' to Gum 514 lks Mount Arthur Observations for Meridian William Jone 40 ac. C.P. 1060 980 1100 730 1070 530 1440 350 190°00 204°45 161° 33 172° 28 203° 47 filled 0 Sur the 293° 47' 158° 32' 206° 17' 123° 13 600 375 2160 2430 2250 1200 1630 by Thereby certify that I in person made and on the 10th October 1900 completed the survey represented on this plan on which are written the bearings and lengths of eccordance with the regulations published for the guidance of Licensed Surveyors and the practice of the Department of Lands Azimuth taken from ab Thomas Williams Scale 20 chains to 1 inch